

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

**Well Plugging Record**  
**K.A.R. -82-3-117**

API NUMBER 15-185-23333-0000  
LEASE NAME McIlvain  
WELL NUMBER 1-11

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

*KCC BEM 12-27-05 1240*  
*RBOMS 2310 1260*  
*CP43*  
780 Ft. from N South Line of Section  
1260 Ft. from E West Line of Section

LEASE OPERATOR Mull Drilling  
ADDRESS P.O. Box 2758 Section 11 Township 21s Range 13w  
CITY, STATE, ZIP Wichita, Kansas 67201-2758 County Stafford  
PHONE # 316-264-6366  
Character of Well Dry and Abandoned Date Well Completed 04/01/05  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Commenced 04/01/05  
Date Plugging Completed 04/01/05 (date)

The plugging proposal was approved on April 1, 2005  
by Richard Lacey (KCC District Agent's Name)

Is ACO-1 Filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_ Yes  
Producing Formation(s) D&A Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3710

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	102			
Redbeds	Shale	102	240	8-5/8"	261.59'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Plugged well on 12/08/05 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel. Bottom plug at 3400' - 40 sx, 2nd plug at 760' - 50 sx, 3rd plug at 310' - 50 sx, top plug at 60' - 20 sx, Rathole - 15 sx, no mousehole. Job completed at 8:00 pm on 12/09/05. Allied Cementing ticket #24728. Plugging orders from Ken Jeblick on 12/08/05. Sterling reported plugging to KCC on 12/09/05.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mull Drilling (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Gary Talbott (Employee of Operator or (Operator) of above described well, being first  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*

**RECEIVED**  
**DEC 13 2005**  
**12-13-05**  
**KCC WICHITA**

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 12th day of December 2005



*Pamela S. Fields*  
(Notary Public)

My Commission Expires: \_\_\_\_\_

*BW*

# Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

## Mcllvain 1-11

**LOCATION:** S/2 SW NW NE  
**API:** 15-185-23333-0000

Section 11 T 21s R 13w  
Stafford County, Kansas

**OWNER:** Mull Drilling  
**CONTRACTOR:** Sterling Drilling Company, Rig #1

**COMMENCED:** 29-Nov-05  
**COMPLETED:** 09-Dec-05

**TOTAL DEPTH:** DRILLER 3710 FEET  
LOGGER 3711 FEET

**Ground Elevation:** 1876  
**KB Elevation:** 1885

### LOG

0 -	2 FEET	Top Soil	<i>From Water Well Driller</i>
2 -	18 FEET	Clay	
18 -	25 FEET	Fine Sand	
25 -	50 FEET	Clay	
50 -	75 FEET	Fine Sand	
75 -	100 FEET	Sand and Gravel	
100 -	720 FEET	Redbeds	
720 -	746 FEET	Anhydrite (Driller's)	
746 -	1550 FEET	Shales and Salt	
1550 -	3650 FEET	Limestone, Shale and Dolomite	
3650 -	3710 FEET	Arbuckle	

### CASING RECORDS

#### Surface Casing-8-5/8"

Spud at 3:00 pm on 11/29/05. Drilled 12-1/4" hole to 275'. Ran 7 joints of new, 20#, 8-5/8" surface casing, tallied 261.59', set at 271' KB. Cemented with 275 sx 70/30 Poz, 2% Gel, 3% CC. Cement did circulate. Plug down at 10:00 pm on 11/29/05. Allied Cementing ticket # 22614. Welder strapped bottom 3 joints together and welded collars on remaining joints.

#### Production Casing

Plugged well on 12/08/05 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel. Bottom plug at 3400' - 40 sx, 2nd plug at 760' - 50 sx, 3rd plug at 310' - 50 sx, top plug at 60' - 20 sx, Rathole - 15 sx, no mousehole. Job completed at 8:00 pm on 12/09/05. Allied Cementing ticket #24728. Plugging orders from Ken Jeblick on 12/08/05. Sterling reported plugging to KCC on 12/09/05.

### DEVIATION SURVEYS

1/4	degree(s) at	275	feet
1-1/4	degree(s) at	3360	feet
3/4	degree(s) at	3710	feet

RECEIVED  
DEC 13 2005  
KCC WICHITA