

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

RECEIVED  
DEC 23 2005

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

KCC WICHITA

Lease Operator: John O. Farmer, Inc.

Address: P.O. Box 352, Russell, KS 67665

Phone: (785) 483-3144 Operator License #: 5135

Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: \_\_\_\_\_ (Date)

by: District #4 (Darrel Dipman witnessed plugging for KCC) (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Howard Depth to Top: 3539' Bottom: 3700' T.D. 3700'

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-179-20,677-00-00

Lease Name: Hoxie Waterflood

Well Number: Tract 2, Well 3

Spot Location (QQQQ): \_\_\_\_\_ - N/2 - S/2 - SE

990 Feet from  North /  South Section Line

1320 Feet from  East /  West Section Line

Sec. 36 Twp. 8S S. R. 29  East  West

County: Sheridan

Date Well Completed: 5-7-83

Plugging Commenced: 12:45 P.M., 12-9-05

Plugging Completed: 3:45 P.M., 12-9-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Howard	oil & water	3611'	3618'	8-5/8"	281'	-0-
				4-1/2"	3699'	-0-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing @ 2770' - mixed 75 sks. cement w/300# hulls and pumped down the tubing to 2770'. Pulled tubing to 1800' - mixed 50 sks. cement w/150# hulls and pumped down the tubing to 1800'. Pulled the tubing on up to 910' & mixed 60 sks. cement w/50# hulls - cement did circulate. Pulled the remaining tubing out of the hole and topped the well off w/20 sks. cement. Finished plugging the well by pumping 10 sks. of cement down the backside of the casing - pressured to #300#.

Name of Plugging Contractor: Allied Cementing Company, Inc. Joe Servicing Inc License #: 3152

Address: P.O. Box 31, Russell, KS 67665

Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.

State of Kansas County, Russell, ss.

John O. Farmer III (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 21st day of December, 20 05

Margaret A. Schulte My Commission Expires: \_\_\_\_\_  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*bu*