

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD KCC WICHITA K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc. Address: P. O. Box 783188 Phone: (316) 691-9500 Operator License #: 4767 Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 12-20-2005 by: Mike Maier (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (If needed attach another sheet) Mississippian Depth to Top: 4407' Bottom: 4436' T.D. 4436'

API Number: 15-135-30047-00-01 Lease Name: Moore D Well Number: #4 Spot Location (QQQQ): 150' W of - C - SE - NW 1980 Feet from [X] North / [] South Section Line 1830 Feet from [] East / [X] West Section Line Sec. 30 Twp. 19 S. R. 21 [] East [X] West County: Ness Date Well Completed: 06/04/1965 original well Plugging Commenced: 12/20/2005 Plugging Completed: 12/21/2005

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Mississippian, Oil & Water, 4407', 4436', 8.625", 506', -0-. Row 2: (blank), (blank), (blank), (blank), 4.50", 4435', -0-.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2" tubing to 4300'. Pumped 35 sx 60/40 Pozmix cement + 6% gel + 150 # Hulls down tubing. Pulled tubing out of hole. Set cast-iron bridge plug at 1300'. Perforated 4.50" casing at 650' w/ 2 shots. Pumped 135 sx. 50/40 Pozmix cement + 6% gel down 4.50" casing; cement circulated to surface up 4.50" annulus.

Plugging complete at 12:30 PM on 12-21-05, witnessed and approved by Mike Maier w/ the KCC.

Name of Plugging Contractor: Allied Cementing H-D Oilfield Services License #: 32970 Address: P. O. Box 31 Russell, KS 67665

KCC BEN 1-18-06 Per CP 2/3 Cement Ticket

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc.


State of Kansas County, Ness, ss.

John Niernberger - employee of Ritchie Exploration, Inc.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address) P. O. Box 783188 Wichita, KS 67278-3188



Subscribed and SWORN TO before me this 17 day of January, 20 06 My Commission Expires: 10-14-07 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bem

ALLIED CEMENTING CO., INC.

22622

RECEIVED

JAN 18 2006

KCC WICHITA

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Great Bend

DATE <i>12-21-05</i>	SEC <i>30</i>	TWP. <i>19</i>	RANGE <i>21 W</i>	CALLED OUT <i>6 AM</i>	ON LOCATION <i>8 AM</i>	JOB START <i>9 AM</i>	JOB FINISH <i>12 AM</i>
LEASE <i>MOORE</i>	WELL# <i>D-PA</i>	LOCATION <i>Bazine 5 1/2 S E15</i>			COUNTY <i>MOSS</i>	STATE <i>K.S.</i>	
<input checked="" type="radio"/> OLD <input type="radio"/> NEW (Circle one)							

CONTRACTOR *H+D well*

TYPE OF JOB *old Hole Plug*

HOLE SIZE _____ T.D. _____

CASING SIZE *4 1/2"* DEPTH _____

TUBING SIZE *2"* DEPTH *4300 ft*

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER _____

CEMENT AMOUNT ORDERED *170 50 60 gal*

200 # Hull

EQUIPMENT

PUMP TRUCK CEMENTER *Mike M*

181 HELPER *Rick H*

BULK TRUCK DRIVER *Steve T*

341 DRIVER _____

COMMON	<i>102 gal.</i>	@	<i>8.70</i>	<i>887.40</i>
POZMIX	<i>68 gal.</i>	@	<i>4.70</i>	<i>319.60</i>
GEL	<i>9 gal.</i>	@	<i>14.00</i>	<i>126.00</i>
CHLORIDE		@		
ASC		@		
<i>HULLS</i>	<i>200 #</i>	@	<i>2.10</i>	<i>420.00</i>
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<i>172 gal.</i>	@	<i>1.60</i>	<i>275.20</i>
MILEAGE	<i>172 mi</i>	@	<i>1.17</i>	<i>199.00</i>
TOTAL				<i>1830.20</i>

REMARKS:

Mix 35 gal with 150 # Hull at 4300 ft

Mix 135 gal Down The 4 1/2 pos. rig

Great Bridge plug at 1300 ft shot hole at 650 ft

SERVICE

DEPTH OF JOB	<i>4300 ft</i>			
PUMP TRUCK CHARGE				<i>750.00</i>
EXTRA FOOTAGE		@		
MILEAGE	<i>17</i>	@	<i>5.00</i>	<i>85.00</i>
MANIFOLD		@		
		@		
		@		
TOTAL				<i>835.00</i>

CHARGE TO: *Ritchie Expro*

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

	@			
	@			
	@			
	@			
	@			
TOTAL				

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE *Beannie Dills*

PRINTED NAME

Thank you 442