

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24890-0000

LEASE NAME Weber

WELL NUMBER 1

1,320 Ft. from ^N Section Line

1,450 Ft. from E Section Line

SEC. 21 TWP. 16 RGE. 12 KEX or (W)

COUNTY Barton

Date Well Completed 1-8-06

Plugging Commenced 1-8-06

Plugging Completed 1-8-06

RECEIVED
JAN 19 2006
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Palomino Petroleum, Inc.

ADDRESS 4924 SE 84th St., Newton, KS 67114

PHONE# (316) 799-1000 OPERATORS LICENSE NO. 30742

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-7-06 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3,410'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	410'	Cmtd. w/250 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Push bridge plug to 850', pump 25 sax on plug thru drill pipe; push bridge plug to 475', pump 50 sax on plug thru drill pipe; push wiper plug to 40', dump 10 sax on plug to cellar. Dump 15 sax down rat hole and 10 sax down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PALOMINO PETROLEUM, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor (Employee of ~~XXXXXXXX~~ or ~~XXXXXXXXXX~~)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) Jack P Beeman

(Address) Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 16th day of January, 2006

My Commission Expires: _____



Ruth Phillips
Notary Public




Shields

Russell, Kansas

WELL LOG

Operator: Palomino Petroleum, Inc.
 Well: Weber #1
 Commenced: December 19, 2005
 Completed: January 8, 2006
 Contractor: Shields Drilling Co.

Well Description: 1,320' FNL, 1,450' FEL,
 NE/4 Sec. 21-16S-12W
 Barton County, KS



CASING RECORD		
Size	Run	Pulled
8 5/8"	410'	Cmtd. w/250 sax

Elevation: 1,926' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Surface clay, sand, shale	140'	
Shale	730'	
Redbed	1,214'	
Shale	2,270'	
Shale & lime	3,105'	
Lime	3,410'	RTD

RECEIVED
 JAN 19 2006
 KCC WICHITA

Notes