

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21962-00-00
Spot: NWSENW Sec/Twnshp/Rge: 13-15S-19W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: DECHANT Well #: 2
County: ELLIS Total Vertical Depth: 3670 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------|
| PROD | 5.5 | 3668 | 0 | w/150 sxs cmt |
| SURF | 8.625 | 260 | 0 | w/175 sxs cmt |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/17/2006 8:30 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 1235' w/375 sxs cement.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/17/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 300' - 1250' - 1900'.
Hooked up to the annulus and pumped 10 sxs cement.
S.I.P. 500#.
Swaged onto 5 1/2" - mixed and pumped 275 sxs cement with 500# hulls.
Max. P.S.I. 700#. S.I.P. 500#.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

JAN 18 2006

RECEIVED
JAN 20 2006
KCC WICHITA

ROY VONFELDT
 524 ST JOHN
 RUSSELL, KS 67665
 CONTR DUKE DRILLING CO CTY ELLIS
 GEOL JERRY KNOBEL FIELD DECHANT SOUTH

13-15-19W
 NW SE NW

E 2024 KB CM 4/16/80 CARD ISSUED 7/18/80 IP P 14 BOPD, NW
 2021 DF CONG 3624-28
 API 15-051-21,962 (NEW PAY)

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

| SMP | TOPS | DEPTH | DATUM |
|----------|------|-------|-------|
| ANH | | 1209 | + 815 |
| B ANN | | 1252 | + 772 |
| HEEB | | 3270 | -1246 |
| TOR | | 3289 | -1265 |
| LKC | | 3317 | -1293 |
| BKC | | 3565 | -1541 |
| CHT CONG | | 3613 | -1589 |
| CONG SD | | 3631 | -1607 |
| ARB | | 3652 | -1628 |
| RTD | | 3670 | -1646 |
| NO LOG | | | |
| | | | |
| | | | |
| | | | |
| | | | |

8-5/8" 260/175sx, 5 1/2" 3668/150sx
 DST (1) 3469-3517 (LKC)/30-30-0-0,
 18" M W/FEW SPKS O, ISIP 96#,
 IFP 43-43#
 DST (2) 3538-3638 (CONG)/60-30-60-30,
 915' HO&GCM, SIP 992-887#, FP 106-
 309/372-426#
 MICT - CO, PF (CONG) 3624-28, NAT, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS