

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22827-00-02
Spot: NESENWNW Sec/Twnshp/Rge: 24-19S-14W
4480 feet from S Section Line, 4210 feet from E Section Line
Lease Name: EVERS Well #: 2
County: BARTON Total Vertical Depth: 3471 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3464	0	175 SX CMT
SURF	8.625	791	0	400 SX CMT

81
#112

Well Type: EOR UIC Docket No: E26863.2 Date/Time to Plug: 01/06/2006 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTRYE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2006 2:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off casing to 3265' and topped with 5 sxs cement using a dump bailer.
Cut casing off at 2205'.
Pulled up to 1650' - mixed and pumped 120 sxs cement with 300# hulls.
Pulled up to 790' - spotted 40 sxs cement with 100# hulls.
Pulled up to 250' and circulated cement with 60 sxs.
POOH. Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
3396	3402		
3356	3359		
3332	4354		
3316	3323		
0	0		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 1-23-06
INV. NO. 2006060993

RECEIVED

JAN 23 2006

KCC WICHITA

Form CP-2/3

JAN 19 2006

VINCENT OIL CORPORATION

KSB&T BLDG. #1110

#2 "A" EVERS

24-19-14W

WICHITA, KS. 67202

800' FNL &


1070' FWL, NW/4

CONTR MURFIN DRILLING CO.

CTY BARTON

GEOL LARRY FRIEND

FIELD ESS



ELV 1871 KB SPD 6/28/82

CARD ISSUED 9/30/82

IP P 75 BOPD & NW

1866 GL

LANS 3316-3402 OA

API 15-009-22,827

LOG	Tops	Depth/Datum
ANH	783	+ 1088
TOP	2752	- 881
HEEB	3088	- 1217
TOR	3102	- 1231
BR LM	3184	- 1313
LKC	3199	- 1328
STK	3370	- 1499
BKC	3424	- 1553
ERO ARB	3464	- 1593
LTD	3467	- 1596
RTD	3471	- 1600

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

8 5/8 " 791/400SX; 5 1/2 " 3464/175SX

DST (1) 2998-3043 / 30-45-45-60, REC 60' GCM, W / FEW OIL SPKS, 180' GCWM, 300' GSY WTR, SIP 1076-1076#, FP 74-148 / 210-272#

DST (2) 3305-3348 / 30-45-30-60, GTS / 38", (2ND OPEN) GA 89.8 MCFG / 2", STAB AT 34.7 MCFG / 27", REC 60' O & GCM (38% M, 15% OIL, 47% G), EST 300' HG & SMCO, 180' CL GSY OIL (GR 43%), 60' VSMCO (1% M), 120' FROTHY OIL, SIP 691-691#, FP 88-132 / 110-143#

CORE (1) 3348-3364, FULL REC, DETAILS NA

CORE (2) 3397-3426, FULL REC, DETAILS NA

DST (3) 3391-3426 / 45-45-30-45, REC 65' HG & SOCM (57% G, 5% OIL, 38% M), SIP 571-341#, FP 55-55 / 66-77#

DST (4) 3423-3471 / 30-45-30-60, 580' GIP, 720' SMCGO (50% OIL, 40% G, 10% M), SIP 995-995#, FP 77-198 / 264-363#

MICT - CO, PF (LANS) 3396-3402, 3356-3369, 3350-3354, 3332-3342 & 3316-3323, AC 4750 G (15%), TSTD, POP, P 75 BOPD, NW (GR 37°)