

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20813-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 23-12S-22W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: STECKLINE Well #: 1  
County: TREGO Total Vertical Depth: 4080 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PKR		1407		
PROD	5.5	4078	1025	200 SX CMT
SURF	8.625	321	0	200 SX CMT

#132<sup>60</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/04/2006 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 325 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/04/2006 2:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Sanded off well - put 5 sxs cement at 1300' - shot 5 1/2" casing off at 1025' - pulled one joint.  
Spotted 175 sxs cement with 200# hulls.  
Pulled to 800' - spotted 25 sxs cement - well pressured up.  
Pulled to 650' - spotted 25 sxs cement with 100# hulls.  
Pulled to 400' - circulated with 100 sxs cement - cellar full.  
Pulled all casing and cellar stayed full.  
Total of 325 sxs 60/40 pozmix - 10% gel and 400# hulls.

Perfs:

Top	Bot	Thru	Comments
4068	4070		
4008	4016		
3738	3742		

Remarks: COPELAND ACID & CEMENTING. QUALITY & ATS-WATER.

Plugged through: CSG

District: 04

Signed

Roger L. Moses

(TECHNICIAN)

INVOICED

DATE

1-23-06

INV. NO

2006060-988

RECEIVED

JAN 23 2006

KCC WICHITA

Form CP-2/3

JAN 19 2006

