

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03077-00-00

Spot: NESENE

Sec/Twnshp/Rge: 28-14S-19W

3630 feet from S Section Line,

330 feet from E Section Line

Lease Name: FEITZ

Well #: 3

County: ELLIS

Total Vertical Depth: 3801 feet

Operator License No.: 30606

Op Name: MURFIN DRILLING CO., INC.

Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3798	0	w/unknown sxs cmt
SURF	8.625	203	0	w/unknown sxs cmt

53
\$123

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/11/2006 9:00 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: MIKE STATON

Company: MURFIN DRILLING CO., INC.

Phone: (785) 483-9633

Proposed 01/10/2006 - Acidized hole with 5 BBL acid - hole went on vacuum.

Plugging 01/11/2006 - Ordered 350 sxs 60/40 pozmix - 10% gel - 500# hulls.

Method: DV Tool at 1475' w/475 sxs cwc.

2 7/8" tubing parted in hole.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/12/2006 9:30 AM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

01/11/2006 - Rigged to 8 5/8" casing - pressured to P.S.I. 1000#.

Murfin RIH with tubing to 854'.

Allied rigged to tubing and pumped 80 sxs 60/40 pozmix neat, followed with 70 sxs 60/40 with 300# hulls mixed in to circulate cement to surface.

Pulled tubing - tied onto 5 1/2" casing with a swedge and pumped 200 sxs 60/40 pozmix with 200# hulls mixed in - staged cement in time intervals.

01/12/2006 - Pumped 25 sxs cement with 200# hulls mixed in.


Max. P.S.I. 600#. S.I.P. 600#.

Remarks: ALLIED CEMENTING COMPANY-TICKET #23531.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE

1-23-06

INV. NO

2006060991

JAN 19 2006

RECEIVED

JAN 23 2006

KCC WICHITA

Form CP-2/3

FRONTIER OIL COMPANY

#3 FEITZ

28-14-19W
NE SE NE

Contr. RED TIGER DRLG

ELLIS

County

E. 2205RB Comm.

Comp. 12-11-59

IP

99 BOPD

Tops	Depth	Datum
ANH	1465	+740
HEEB	3447	-1242
LANS	3493	-1288
ARB	3797	-1592
TD	3801	-1596


Casing

8" 203

5" 3798

DST 3558-76/2 HR, 540' SW, BHP
1260#DST 3608-3693/2 HR, 640' G, 260'
HO & GCM, BHP 880#DST 3797-3801/1 HR, 280' G,
2130' O, BHP 1120#CO TD: SWB 12 1/2 BOPH, NATL/4 HRS
KRAUS

NW

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

MAILED