

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24310-00-00  
Spot: NWSENWSW Sec/Twnshp/Rge: 36-13S-20W  
1915 feet from S Section Line, 4405 feet from E Section Line  
Lease Name: ENGEL C Well #: 2  
County: ELLIS Total Vertical Depth: 3967 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3967	0	w/200 sxs cmt
SURF	8.625	302	0	w/175 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/04/2006 9:30 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 295 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/04/2006 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

DV Tool at 1625' w/unknown amount of cement.  
Ran tubing to 2175' - circulated with 220 sxs cement with 200# hulls.  
Pulled all tubing - squeezed w/75 sxs cement and 200# hulls.  
Max. P.S.I. 750#. S.I.P. 300#.  
Annulus pressure to 500# - took no cement.  
Total of 295 sxs 60/40 pozmix - 10% gel - 400# hulls.

Remarks: ALLIED CEMENTING COMPANY. POE WELL SERVICE-WATER.

Plugged through: TBG

District: 04

Signed Roger L. Moses  
(TECHNICIAN)

RECEIVED

JAN 19 2006

KCC WICHITA

Form CP-2/3

JAN 09 2006

ACO-1

replacement card

RAPID WELL SERVICE  
RUSSELL, KS 67665

36-13 -20W  
1915'FSL & 875'FWL, SW/4

#2 "C" ENGEL

site: 2-1/4 S & 3-1/2 W OF YOCEMENTO, KS      city: ELLIS      API 15-051-24310  
 contr: WOODMAN-IANNITTI DRILLING      field: IRVIN  
 geol: J. B. GREEN

fr	spd	drig	card	last
date 09/04/85	date 09/06/85	comp 09/13/85	issued 10/16/86	revised 02/17/88


ELV: 2270 KB SMP
tops.....depth/datum
ANH.....1568 +702
TARK.....3109 -839
ELMCNT.....3152 -882
HOW.....3222 -952
TOP.....3280 -1010
HEEB.....3533 -1263
TOR.....3554 -1284
LANS.....3574 -1304
KC.....3823 -1553
MARM.....3856 -1586
CONG.....3885 -1615
ARB.....3915 -1645
PBTD.....3886 -1616

IP status:  
 OIL, P 5 BO & 480 BWP, LKC 3650-3843 , MARM  
 3866-3872 ,  
 CSG: 8-5/8" 302 / 175 SX, 5-1/2" 3967 / 200 SX  
 NO CORES  
 DST (1) 3909-3920 (ARB), / 30-30-60-30, REC 495' OILY  
 WM, 550' OILY W, 650' SW, 185' WM ISIP 1950# FSIP  
 1950# IFP 400# -867#  
 MICT - CO, PF (ARB) 3915-3916.5, 3910-3912, W / 4  
 SPF, SWB DWN, NAT, NON-COMMERCIAL, SQZ'D PFS W  
 / 75 SX CMT, CO CMT, PF (MARM) 3872-3878, 3866-  
 3872, W / 2 SPF, AC 1000 GAL (INS), SWB LD, PF (KC)  
 3839.5-3842.5, 3830.5-3833.5, AC (3730-3878 OA) W /  
 3500 GAL (15% INS), SO, SQZ'D PFS (3872-3876) W / 55  
 SX RTD.....3980 -1710 (over)

COPYRIGHT 1988

RAPID WELL SERVICE  
RUSSELL, KS 67665

36-13 -20W  
1915'FSL & 875'FWL, SW/4

#2 "C" ENGEL

CMT, CO CMT, PF (LKC) 3777-3782, 3770-3772, 3650-3653, W / 2 SPF, SO, NAT, SQZ'D (2797)  
 W / 50 SX CMT, CO CMT, SET 2-7/8" TBG & PKR AT 3875, POP, P 5 BO & 480 BWP, 10/15/85,  
 COMMINGLED

CORRECTION & INFO RELEASED: 2/17/88 - WAS ARB PAY  
 IN ERROR; ADDED WELL INFO