

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-19104-00-01  
Spot: E2NESE Sec/Twnshp/Rge: 36-13S-20W  
1980 feet from S Section Line, 330 feet from E Section Line  
Lease Name: ENGEL B OWWO Well #: 2  
County: ELLIS Total Vertical Depth: 3907 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	0	0	W/UNKNOWN SXS
SURF	8.625	224	0	W/UNKNOWN SXS

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2005 12:30 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered 350 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/28/2005 3:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Ran tubing to 960' - 75 sxs to circulate.  
Pulled tubing and squeezed 5 1/2" with 175 sxs cement with 400# hulls.  
Max. P.S.I. 750#. S.I.P. 400#.  
Tied to 8 5/8" x 5 1/2" annulus and squeezed with 50 sxs cement and 100# hulls.  
Max. P.S.I. 100#. S.I.P. 100#.  
Total of 300 sxs 60/40 pozmix - 10% gel and 500# hulls.

Remarks: ALLIED CEMENTING COMPANY. POE WELL SERVICE-WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses  
(TECHNICIAN)

RECEIVED

JAN 19 2006

KCC WICHITA

Form CP-2/3


JAN 05 2006

W. J. COPPINGER #2 ENGEL 'B' 36-13-20W  
 E2 NE SE  
 Contr. W. J. COPPINGER ELLIS County  
 E. 2261 RB Comm. Est 7-10-57 Comp. 8-2-57 IP D & A

Tops	Depth	Datum
ANH	1550	711
HEEB	3512	-1251
TOR	3534	-1273
LANS	3552	-1291
B/KC	3809	-1518
CONG	3861	-1600
ARB	3905	-1611
TD	3907	-1616

Casing  
 8" 224  
 DST 3731-40/1 HR, 30' M, F  
 SPKS 0, BHP 310#  
 DST 3888-3907/1 HR, 20' M  
 F SPKS 0, BHP 20#

IRVIN POOL



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS