

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-181-20022-00-01  
Spot: NESWNESE Sec/Twnshp/Rge: 3-6S-37W  
1874 feet from S Section Line, 766 feet from E Section Line  
Lease Name: HARTLEY Well #: 5  
County: SHERMAN Total Vertical Depth: 4827 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH STREET  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4822	0	w/176 sxs cmt
SURF	8.625	401	0	w/250 sxs cmt

#156<sup>88</sup>

Well Type: EOR UIC Docket No: E27294.2 Date/Time to Plug: 01/06/2006 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE FRITZLER Company: FRITZLER TRUCKING, INC. Phone: (785) 798-3641

Proposed Plugging Method: Ordered 410 sxs 60/40 pozmix - 10% gel and 500# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/06/2006 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 401' w/250 sxs cement.  
5 1/2" production casing set at 4822' w/176 sxs cement.  
PBSD 4760'. TD 4827'.  
Ran tubing to 2160' - pumped 340 sxs cement with 300# hulls - cement circulated.  
Pulled tubing to surface - connected to 5 1/2" casing - pumped 35 sxs cement.  
Max. P.S.I. 400#. S.I.P. 0#.  
Connected to 8 5/8" surface casing - pumped 40 sxs cement.  
Max. P.S.I. 300#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
4481	4485		

Remarks: ALLIED CEMENTING COMPANY-TICKET #22253.

Plugged through: TBG

District: 04

10

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

DATE 1-23-06

INV. NO. 2006060992

RECEIVED

JAN 20 2006

KCC WICHITA

JAN 10 2006

DREILING OIL, INC.  
RR #1, VICTORIA, KS.


#5 HARTLEY

3-6-37W  
150'SW, C NE SE

CONTR CO. TOOLS CTY SHERMAN

GEOL \_\_\_\_\_ FIELD LLANOS

E 3446 KB CM 7/12/76 CARD ISSUED 6/23/77 IP P 25 BOPD  
LANS 4442-46



API 15-181-20,022-00-0

LOG	TOPS	DEPTH	DATUM
ANH		3114	+ 332
TOP		4088	- 642
HEEB		4246	- 800
TOR		4294	- 848
LKC		4304	- 858
BKC		4584	-1138
MARM		4598	-1152
PAWN		4690	-1244
ET SC		4748	-1302
CHER SH		4777	-1331
CHER SD		4820	-1374
RTD		4827	-1381

8-5/8" 401/250sx, 5 1/2" 4822/176sx  
DST'S NOT RELEASED  
MICT - PF 4442-4446, AC 500, REC LD &  
SWB 20 BO/4 HRS, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA KANSAS

11/20/77