

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1
Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-005-20702-00.01 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: McCoy Petroleum Corporation KCC LICENSE # 5003
(owner/company name) (operator's)

ADDRESS: 8080 E. Central CITY: Wichita
STATE: Kansas ZIP CODE: 67206 CONTACT PHONE: 316-636-2737
LEASE: Leiss GU 'A' WELL# 212 OWWO Section 12 Township 27s Range 18w
NW SW SPOT LOCATION/QQQQ COUNTY: Kiowa
1980 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)
660 FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS _____
SURFACE CASING SIZE 8-5/8" SET AT 352 CEMENTED WITH 325 SACKS _____
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS _____

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 2153 G.L. 2162 K.B. T.D. 908 PBD _____ Anhydrite Depth ???
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Plugged well on 12/20/05 in this manner: Heavy mud in hole and between all plugs. Used 135 sx of
of 60/40 Poz, '6% Gel. Bottom plug at 840' - 40 sx, 2nd plug at 400' - 50 sx and top plug at 60' - 20 sx.
Rathole - 15 sx and mousehole-10 sx. Job completed at 3:30 pm on 12/20/05. Acid services ticket #11421.
Plugging orders from Mike Maier on 12/20/05. Sterling reported plugging to KCC on 12/21/05.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Lonnie Saloga/Gary Talbott Phone#: (620) 672-9508
Address: P.O. Box 1006 City: Pratt State: Kansas
PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)
Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 3:30 pm on December 20, 2005. Plugged
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 12/20/05 AUTHORIZED OPERATOR OR AGENT: _____
(signature) Gary M. Talbott, Agent for Operator

RECEIVED
DEC 30 2005
KCC WICHITA

CASING RECORDS

Surface Casing Data:

Existing 8-5/8" casing set at 352'. Plugged on 12/01/80 by Cinco Exploration. Plugs are :
10 sks at 40', 30sxs and plug at 350' and 50 sks at 550'. Heavy mud to 4830'.

Plugging Data:

Plugged well on 12/20/05 in this manner: Heavy mud in hole and between all plugs. Used 135 sx of
of 60/40 Poz, '6% Gel. Bottom plug at 840' - 40 sx, 2nd plug at 400' - 50 sx and top plug at 60' - 20 sx.
Rathole - 15 sx and mousehole-10 sx. Job completed at 3:30 pm on 12/20/05. Acid services ticket #11421.
Plugging orders from Mike Maier on 12/20/05. Sterling reported plugging to KCC on 12/21/05.

DEVIATION SURVEYS

None Taken

RECEIVED
DEC 30 2005
KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Leiss GU 'A' 2-12 OWWO

LOCATION: NW SW *KCC ajs*
API: 15-095-20702-00.01

Section 12 T 27s R 18w
Kiowa County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 19-Dec-05
COMPLETED: 20-Dec-05

TOTAL DEPTH: DRILLER

908

 FEET
LOGGER

No Log

 FEET

Ground Elevation: 2153
KB Elevation: 2162

LOG

10' to 45' Open hole
40' to 95' Hard Cement
95' to 305' Open hole
305' to 360' Hard Cement
360' to 472' Hard Cement (Drilling fluid clear water w/ no color)
472' to 908' Drilling fluid turned red (Drilling new hole)

CASING RECORDS

Surface Casing Data:

Existing 8-5/8" casing set at 352'. Plugged on 12/01/80 by Cinco Exploration. Plugs are :
10 sks at 40', 30sxx and plug at 350' and 50 sks at 550'. Heavy mud to 4830'.

Plugging Data:

Plugged well on 12/20/05 in this manner: Heavy mud in hole and between all plugs. Used 135 sx of
of 60/40 Poz, '6% Gel. Bottom plug at 840' - 40 sx, 2nd plug at 400' - 50 sx and top plug at 60' - 20 sx.
Rathole - 15 sx and mousehole-10 sx. Job completed at 3:30 pm on 12/20/05. Acid services ticket #11421.
Plugging orders from Mike Maier on 12/20/05. Sterling reported plugging to KCC on 12/21/05.

DEVIATION SURVEYS

None Taken

RECEIVED
DEC 30 2005
KCC WICHITA