

6 070504

PLUGGED 204 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065, 22, 219 0000
5 1/2 - N 1/2 - SE, SEC. 21, T 7 S, R 22 W
1650 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Worcester Well # 1

Operator: Abercrombie Drilling, Inc.
Name & Address: 801 Union Center
Wichita, Kans. 67201
Jack Partridge

County Graham 121.23
Well Total Depth 2730 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 289

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____ Tag # 179

Plugging Contractor Abercrombie Drilling, Inc. License Number # 5422

Address 801 Union Center, Wichita, Kans 67202

Company to plug at: Hour: 12:30 PM Day: 28th Month: August Year: 19 86

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc (phone) 316-262-1841

were: 8 5/8" - 289' ET SP. CMC #185 SK cmt. By B.J. Titan

Request 26-205 5/40 Formix Gel - Ca-Cl - 1 SK cello Slake and 8 5/8" Plug
Spotted with Drill Stem, Reconditioned Hole, Heavy mud Between all plugs.
Elev. 2218, Ink, 1855, Mud Condition Viscosity 46, Weight 9.3,
Water Loss 11.2, Maly said they did not penetrate. Cible, Pappal.

30 SK @ 1870'
100 SK @ 1060'
50 SK @ 330'
10 SK @ 40' - 15 SK Pat Hole
Plugging Proposal Received by M. Schubert (TECHNICIAN)

Plugging Operations attended by Agent? All Part _____ None _____

Operations Completed: Hour: 2:15 PM Day: 28th Month: August Year: 19 86

ACTUAL PLUGGING REPORT Ordered 205 5/40 Formix Gel - Ca-Cl - 1 SK cello Slake

and 8 5/8" Plug, Reconditioned Hole, Spotted with Drill Stem,
Heavy mud Between all plugs

1st Plug @ 1870' ET #1/30 SK cmt, 2nd Plug @ 1060' #1/100 SK cmt
#1 5/8" Slake Mud In, 3rd Plug @ 330' ET #1/50 SK cmt, 4th Plug @
40' #1/10 SK cmt 15 SK in Pat Hole (circulati)

Remarks: Cemented by B.J. Titan

(If additional description of well is necessary, use BACK of this form.)

INVOICED

DATE SEP 8 1986

INV. NO. 14890

SEP - 5 1986 9/5/86

M. Schubert (TECHNICIAN)

(Plugging Proceed) Gilbert Baltazar witnessed the above well. FORM CP-2/3 Rev. 01-84