

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22667-00-00
Spot: S2N2SW Sec/Twnshp/Rge: 2-7S-23W
1650 feet from S Section Line, 3960 feet from E Section Line
Lease/Unit Name: FT HAYS Well Number: 1
County: GRAHAM Total Vertical Depth: 3926 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 258
Production: Size 4.5 feet: 3925
Liner: Size feet:
\$127.60

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/28/2002 2:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 420 cu.ft. cement slurry.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/28/2002 3:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 258' w/150 sxs cwc. 4 1/2" set at 3925' w/75 sxs.
Port collar at 2136' w/450 sxs cwc.
Prod. LKC.
Fluid level near bottom - depleted production zone.
Filled 4 1/2" with 420 cu.ft. cement slurry.
Plug complete.

RECEIVED
APR 19 2002
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

DATE

4-22-02

NO. 2002061681

Form CP-2/3

APR 15 2002

STATE: KANSAS COUNTY: GRAHAM REISSUE 2-7S-23W
FIELD: MOUNT ETNA NORTH 1 MI N MOUNT ETNA FLD S2 N2 SW
OPER: NORTHERN LIGHTS OIL 1650 FSL 1320 FWL SEC
WELL: 1 FT HAYS WELL CLASS: WFD ELEV: 2453 KB
API: 15-065-22667 STATUS: OIL 2445 GR
SPUD: 07/15/92 COMP: 11/19/92
DTD: 3926 LTD: 3926 FTD: PENNSYLVANIAN PBDT:

LOC: 7 1/2 MI N HILL CITY, KS

IP: COMP 11/19/92, IPP 22 BO, 128 BWPD, GTY 39 **PROD ZONE-** LANSING-KANSAS
CITY 3777-3874 (GROSS)
NO CORES, FOUR DSTS (LANSING-KANSAS CITY DISCOVERY-NEW FIELD)

LOG TOPS:

STONE CORRAL	2107 346	LANSING-KANSAS CITY	3711 -1258
HEEBNER	3672 -1219	B/ KANSAS CITY	3906 -1453
TD	3926 -1473		

LOG TYPES: GRDL;

CSGS: 8 5/8 @ 258 W/150 SX, 4 1/2 @ 3926 W/75 SX; **TBG:** 2 3/8 @ 3905; DRLG COMP
07/21/92 RIG REL 07/21/92

DSTS: **DST #** 1 (LANSING-KANSAS CITY) 3703-3718, OP 30 MIN, SI 30 MIN, OP 30 MIN, SI
30 MIN, REC: 30 FT SOCM, 1970 FT GCSWTR, IFP 91, FFP 495, IFP 539,

(OVER)

COPYRIGHT 1993 PETROLEUM INFORMATION CORPORATION

DATE 03/26/93 CARD # 00035-KS

STATE: KANSAS COUNTY: GRAHAM REISSUE 2-7S-23W
FIELD: MOUNT ETNA NORTH 1 MI N MOUNT ETNA FLD S2 N2 SW
OPER: NORTHERN LIGHTS OIL 1650 FSL 1320 FWL SEC
WELL: 1 FT HAYS WELL CLASS: WFD
(CONTINUED)

REISSUE TO CORRECT FIELD REPLACES CARD ISSUED 2/11/93