

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22707-00-00
Spot: CNESW Sec/Twnshp/Rge: 2-7S-23W
1980 feet from S Section Line, 3330 feet from E Section Line
Lease/Unit Name: FORT HAYS Well Number: 2
County: GRAHAM Total Vertical Depth: 3920 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 274
Production: Size 4.5 feet: 2130
Liner: Size feet:

Well Type: SWD UIC Docket No: D26818.0 Date/Time to Plug: 02/28/2002 3:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 200 cu.ft. cement slurry.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/28/2002 4:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 274' w/170 sxs cwc. 4 1/2" set at 2130' w/425 sxs cwc.
SWD in C.H.
Fluid level low.
Filled 4 1/2" with 200 cu.ft. cement slurry.
Plug complete.

RECEIVED
APR 19 2002
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

DATE

4-22-02

INV. NO.

2002061681

Form CP-2/3

APR 15 2002

STATE: KANSAS COUNTY: GRAHAM REISSUE 2-7S-23W
FIELD: MOUNT ETNA NORTH C NE SW
OPER: AMERICAN ENERGIES 1980 FSL 1980 FWL SEC
WELL: 2 FT HAYS WELL CLASS: U ELEV: 2446 KB
API: 15-065-22707 STATUS: SERVOG 2441 GR
SPUD: 06/29/93 COMP: 07/29/93
DTD: 3920 LTD: FTD: PENNSYLVANIAN PBDT: 2130

LOC: 6 MI N HILL CITY, KS

IP: COMP 7/29/93, SWTR DISP WELL DISP ZONE - CEDAR HILLS 1690-1820(GROSS)
NO CORES, ONE DST

LOG TOPS:
STONE CORRAL 2096 350 | LANSING 3709 -1263
HEEBNER 3670 -1224 | B/ KANSAS CITY 3904 -1458
TD 3920 -1474 |

LOG TYPES: CBND, GRDL;

CSGS: 8 5/8 @ 274 W/170 SX, 4 1/2 @ 2130 W/425 SX; TBG: 2 3/8 @ 1640, W/PKR @ 1640,
DRLG COMP 07/04/93 RIG REL 07/04/93

DSTS: DST # 1 (LANSING) 3770-3790, OP 30 MIN, SI 45 MIN, REC: 60 FT GAS, 30 FT OIL, 120 FT OWCM, 120 FT SWTR, IFP 29, FFP 49, IFP 68, FFP 68,
ISIP 986, FSIP 127, TOOL DIDN'T CLOSE ON FINAL SI;

(OVER)

COPYRIGHT 1993 PETROLEUM INFORMATION CORPORATION

DATE 09/17/93 CARD #00020-KS

STATE: KANSAS COUNTY: GRAHAM REISSUE 2-7S-23W
FIELD: MOUNT ETNA NORTH C NE SW
OPER: AMERICAN ENERGIES 1980 FSL 1980 FWL SEC
WELL: 2 FT HAYS WELL CLASS: U
(CONTINUED)

PERFS: PERF (CEDAR HILLS), 1690-1760, 1790-1820, W/1 PF, TREATMENT NOT RPTD
DRLG COMMENTS: AMERICAN ENERGIES TOOK OVER OPERATIONS @ TD TO CONVERT
TO SWDW

OPER ADD: 155 N MARKET STE 710, WICHITA, KS, 67202 PHONE (316) 263-5785;
CONTR: MALLARD DRLG RIG, # 1
WELL ID CHANGES: OPR CHGD FROM NORTHERN LIGHTS OIL;
REISSUED TO CORRECT TGB & PROD TEST REPLACES CARD ISSUED