

15-065-21716-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-065-21,716

NE-SW-NE, Sec. 2, T 7 S, R 23 W

1650 feet from 018 section line

1650 feet from 10E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name ENDOWMENT Well # A-1

Operator: F. & M. OIL CO, INC  
Name &  
Address 422 UNION CENTER  
WICHITA, Mo. 67202

County GRAHAM

Well Total Depth 3916 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 248

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor ABERCROMBIE DRUG. INC License Number 179

Address 801 UNION CTR. WICHITA, Mo. 316-262-2841

Company to plug at: Hour: 12:30 AM Day: 14th Month: DEC. Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO DENNIS SPORING

(company name) ABERCROMBIE DRUG. INC (phone) 316-262-2841

were: 8 5/8" - 248 FT SP. CUL. 1/170 ST COMMON - 2% GEL - 3% CA-CL. (SUN)

ORDER 180 ST 50 Formix 6% GEL - 3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 2100 FT 1/20 ST CMT. 2nd PLUG @ 1350 FT 1/100 ST CMT.

3rd PLUG @ 250 FT 1/40 ST CMT. 4th PLUG SOLID BRIDGE HULLS - PLUG @ 40 1/20 1/10 ST CMT.

10 ST IN RATE (CIRCULATE)

Signed [Signature] (TECHNICIAN) DOK

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:30 AM Day: 14th Month: DEC. Year: 1982

ACTUAL PLUGGING REPORT ORDERED 180 ST 50 Formix 6% GEL - 3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st PLUG @ 2100 FT 1/20 ST CMT. -> 2nd PLUG @ 1350 FT 1/200 ST CMT.

3rd PLUG @ 250 FT 1/40 ST CMT. -> 4th PLUG SOLID BRIDGE HULLS - PLUG @ 40 1/20 1/10 ST CMT.

10 ST IN RATE (CIRCULATE)

CEMENTED BY SUN CMT.

RECEIVED STATE CORPORATION COMMISSION

DEC 21 1982

Remarks: DID NOT PENETRATE ABERCROMBIE

CONSERVATION DIVISION Wichita, Kansas

12-21-82

I hereby certify that the above plugging instructions were given as herein stated and that I ( ) / did not) observe this plugging.

INVOICED  
DATE 1-13-83  
INV. NO. 2155-W

Signed [Signature] (TECHNICIAN) DOK