

1-21 4-041879

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-065-21,796 0000

SE SW SE /4 SEC. 36, 07 S, 22 W  
330 feet from S section line  
1650 feet from E section line

Operator license# 3715  
Operator: S-B Oil Company  
Address: 3204 Willow  
Hays, Kansas 67601

Lease: Legere Well # 1  
County: Graham 117.91  
Well total depth 3628 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 246 feet  
w/ 170 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 21 Month: January Year 1997

Plugging proposal received from: Gene Karlin

Company: L-K Wirline - Box 1188 - Hays, Ks 67601 Phone: 913-625-6877

Were: 5 1/2" casing set at 3627' w/150 sxs.  
Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 13 sxs gel.  
D.V. Tool at 1665' cwc. O.H. 3406' - 3379' - 3362' - 3314' - 3317' - 3245' - 3249' - 3201' - 3205'.

STATE CORPORATION COMMISSION  
FEB 11 1997  
2/11/97  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 3:00 P.M., Day: 21, Month: January, Year: 1997

Actual plugging report: Pumped down 5 1/2" casing with 25 sxs 60/40 pozmix w/200# hulls, followed with 13 sxs gel, followed with 150 sxs cement with 200# hulls. Pumped down 8 5/8" S.P. - 25 sxs cement with 100# hulls.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD X BAD  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING X, CASING. Elevation: 2116 KB  
Anhy.plug: YES X NO  
Dakota plug: YES X, NO

I did [ X ] / did not [ ] observe the plugging.

Dennis L Hamel  
(agent)

INVOICED  
DATE FEB 13 1997  
INV. NO. 47565