

6040187

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,064 ~~0060~~

NS SW SW, SEC. 34, T 7 S, R 22 (W/E)

feet from N/S section line

feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238

Lease Name Rowe Well # 1

Operator: Petroleum, Inc.

County Graham

Name & Address 300 W. Douglas Suite 800

Well Total Depth 3836 124.67 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 260' w/18 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor DNB Drilling, Inc. License Number 5476

Address 535 N. Oliver, Wichita, Ks. 67208

Company to plug at: Hour: PM Day: 14 Month: September Year: 19 84

Plugging proposal received from John Taylor

(company name) DMB Drilling (phone)

were: Order 200 sks 50/50 pozmix 6% gel 3% cal cl. 1 sk hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 4 PM Day: 13th Month: September Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 1800' w/40 sks

2nd plug @ 1025 w/100 sks w/1 sk hulls

3rd plug @ 275 w/40 sks

4th plug @ 40 w/10 sks

10 sks in Rat Hole

RECEIVED STATE CORPORATION COMMISSION

SEP 17 1984 9/17/84

CONSERVATION DIVISION Wichita, Kansas

Remarks: Cemented by Sun (If additional description is necessary, use BACK of this form.)

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-26-84

INV. NO. 3859

Signed Dennis L. Hamel (TECHNICIAN) SH 44