

6-031583

~~8-4~~ 8-4

283R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,643-06-00  
W/2 SE SW /4 SEC. 3, 7 S, 23 W  
660 feet from S section line  
3135 feet from E section line

Operator license# 5058 Lease Fountain well # 3  
Operator: Griggs Oil Inc. County Graham  
Address: 107 N. Market Well total depth 3840 feet *124.80*  
Suite 800 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 207 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Abercrombie Drilling Inc. License# 5422

Address: Wichita, Kansas 67202

Company to plug at: Hour: \_\_\_\_\_ Day: 4 Month: August Year: 91

Plugging proposal received from: Harold Maley

Company: Abercrombie Drilling Inc. Phone: \_\_\_\_\_

Were: 8 5/8" set @ 207 w/170 sx. Circ. hole with no less than  
36 vis. mud with no loss or gain in fluid. Keep hole full and balance  
plugs with mud. Order 190 sx. 60/40 poz. - 6% gel. - 3% cc. 8 5/8 W.P.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:30P.M., Day: 4, Month: August, Year: 91

Actual plugging report: \_\_\_\_\_

- 1st. plug w/drill pipe @ 2050' w/25 sx.
- 2nd. plug w/drill pipe @ 1250' w/100 sx. plus hulls.
- 3rd. plug w/drill pipe @ 250' w/40 sx.
- 4th. plug w/drill pipe @ 40' w/10 sx. W.P.

Circ. 15 sx. in Rathole.

Remarks: Elev. 2352'. Anhy. 2027' - 60'.

I did[  ] / did not[  ] observe the plugging

RECEIVED  
KANSAS CORPORATION COMMISSION  
*Carl Goodrow*

**INVOICED**

DATE 10-9-91

WEL. NO. 33327

*Carl S.* OCT 8 1991 (agent)  
10-8-91  
CONSERVATION DIVISION  
WICHITA, KS  
Form CP-2/3