

4-30

6 070914

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 065-22,630-00-00
C S/2 NE SW SEC. 3, T 7 S, R 23 W/Ex

1650 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5058

Lease Name Fountain Well # 2

Operator: Griggs Oil Inc.
Name & Address: 107 N. Market #800
Wichita, Ks. 67202
Jim Collins

County Graham 127.07
Well Total Depth 3910 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 30 Month: April Year: 19 91

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling (phone) 316-267-7779

were: 8 5/8 210 ft s.p. cwc w/170 sks. 60/40 poz 3% cc 2% gel Allied.

No arb elv. 2393 Anhy 2052. No circ problems. Mud 43 vis - 9.2 w. 8.4 w.l.

Proposal 190 sks 60/40 poz 6% gel 3% ca cl w/1 sk f.c. spot with drill stem

heavy mud between all plugs. 25 sks at 2060 100 sks w/ 1 f.c. at 1290. 40 sks

at 270 10 sks at 40. 15 sks rathole. Circ.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 12:30PM Day: 30 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Griggs Oil ordered 190 sks 60/40 poz 6% gel

3% ca cl and 1 sk f.c. Circ hole. Spotted and displaced w/drill stem.

1st plug at 2060 ft. w/25 sks cement

2nd plug at 1290 ft w/100 sks w/ 1 sk f.c.

3rd plug at 270 ft. w/40 sks cement.

4th plug at 40 ft. w/10 sks cement 15 sks in rathole. Circ.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

(I did not) observe this plugging.

DATE 5-22-91

INV. NO. 31854

J.S.

Signed Marion J. Schmidt (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
5-20-91
MAY 20 1991
CONSERVATION DIVISION
Wichita, Kansas
5-20-91