

RECEIVED
JAN 18 2006
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - ~~N/A~~ 185-20412-00-00 (Identifier Number of this well), This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 4/18/1972

Well Operator: K & N Petroleum, Inc. KCC License #: 3208
(Owner / Company Name) (Operator's)
Address: 513 West 6th Street City: Ellinwood
State: Kansas Zip Code: 67526 Contact Phone: (620) 793 - 6005
Lease: Sparks Well #: 4 Sec. 6 Twp. 21 S. R. 11 East West
C - W/2 - W/2 - SW/4 Spot Location / QQQQ County: Stafford

983 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
4927 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8" Set at: 265' Cemented with: 210 Sacks
Production Casing Size: 4-1/2" Set at: 3456' Cemented with: 400 gallons Latex-50 sx. cement Sacks

List (ALL) Perforations and Bridgeplug Sets: Simpson 3419'-22'; Arbuckle 3446'-3462'

Elevation: 1824' (G.L. / K.B.) T.D.: 3462 P.B.T.D.: _____ Anhydrite Depth: 550' +/-
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Casing parted 467'. Run tubing to 500' +/- Spot cement. Circulated to surface. Pulled tubing. Pressured up on cement in casing - 350 sacks, 60-40 poz. with 6% gel-400 sacks hulls on location, per Richard Lacey, State KCC agent. Commencing plugging 9:00 AM - 1/8/2006.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Emergency plugging - no log on file.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Edward S. Nemnich
Phone: (620) 587 - 3361

Address: P.O. Box 231 City / State: Claffin, Kansas 67525

Plugging Contractor: D. S. & W. Well Servicing, Inc. KCC License #: 6901
(Company Name) (Contractor's)

Address: P.O. Box 231, Claffin, Kansas 67525 Phone: (620) 587 - 3361

Proposed Date and Hour of Plugging (if known?): 1/8/2006 - 9:00 AM Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/7/2006 Authorized Operator / Agent: Edward S. Nemnich
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202