

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21636-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 8-16S-13W
430 feet from N Section Line, 1980 feet from E Section Line
Lease Name: KRUG Well #: 4
County: BARTON Total Vertical Depth: 3386 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3384	0	w/100 sxs cmt
SURF	8.625	225	0	w/165 sxs cmt

110 ⁰⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/27/2005 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/27/2005 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1800' - 930' - 220'.
Tied onto casing and pumped 225 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Max. P.S.I. 600#. S.I.P. 200#.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3384	3386		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 1-19-06

NO. 2006060983

JAN 09 2006

RECEIVED
JAN 19 2006
KCC WICHITA

AL TIPTON
 BOX 157
 HAYS, KS 67601
 CONTR ALLEN DRLG CO.
 GEOL J. C. MUSGROVE
 #4 KRUG
 8-16-13W
 430' FNL &
 660' FWL, NE/4
 CTY BARTON
 FIELD TRAPP
 E 1932 KB CM 6/11/79 CARD ISSUED 2/14/80 IP P 30 BOPD
 ARB 3383-3386

+		+	
+		+	

API 15-009-21,636

SMP	TOPS	DEPTH	DATUM
ANH		900	+1032
HEEB		3062	-1130
TOR		3083	-1151
DOUG		3096	-1164
LANS		3139	-1207
B KC		3335	-1403
ARB		3381	-1449
RTD		3386	-1454

8-5/8" 225/165sx, 4 1/2" 3384/100sx
 NO LOG
 DST (1) 3357-3386/45-45-45-45, REC 150'
 VHOCM, SIP 1081-1020#, FP 51-71/
 81-102#, HP 1934-1904#
 MICT - CO, PF 3383-3386, AC 250 GAL,
 POP, P 30 BOPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

STAB
 IMAOICED