

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21443-00-00
Spot: N2NE Sec/Twnshp/Rge: 8-16S-13W
660 feet from N Section Line, 1320 feet from E Section Line
Lease Name: KRUG Well #: 1
County: BARTON Total Vertical Depth: 3390 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3387	0	w/125 sxs cmt
SURF	8.625	353	0	w/190 sxs cmt

18
110

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/27/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/27/2005 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perforated at 1800' - 900' - 320'.
Tied onto casing and pumped 180 sxs 60/40 pozmix - 10% gel cement.
Opened backside and circulated with 20 sxs cement.
Closed backside. Pumped 25 sxs cement.
Max. P.S.I. 600#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3387	3390		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED RECEIVED

DATE 1-19-06 JAN 19 2006
INV. NO 2006060983 KCC WICHITA

JAN 09 2006

AL TIPTON
BOX 157, HAYS, KS. 67601

1 KRUG

8-16-13W
C N/2 NE

CONTR ALLEN DRLG. CO. CTY BARTON

GEOL J. C. MUSGROVE FIELD TRAPP

E 1937 KB CM 8/7/78 CARD ISSUED 9/14/78 IF P 60 BOPD, N/W
ARB 3387 $\frac{1}{2}$ -90

+	+	+
+	+	+
+	+	+

API 15-009-21,443

SMP	TOPS	DEPTH	DATUM
*ANH		903	+1034
HEEB		3062	-1125
TOR		3080	-1143
DOUG		3097	-1160
LANS		3142	-1205
BKC		3340	-1403
ARB		3385	-1448
RTD		3390	-1453
*DRILLERS TOP			

8-5/8" 353/190sx, 4 $\frac{1}{2}$ " 3387 $\frac{1}{2}$ /125sx
DST (1) 3362-3390/30-30-30-30, 230' GIP
610' GO, 100' MO, S/P 1091-1081#, FP
112-285#, 295-357#
MICT - CO TD, AC 1000, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS