

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21291-00-00
Spot: S2NWSWSW Sec/Twnshp/Rge: 4-16S-13W
900 feet from S Section Line, 330 feet from W Section Line
Lease Name: MONROE Well #: 4
County: BARTON Total Vertical Depth: 3381 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3378	0	100 SX CMT
SURF	8.625	327	0	195 SX CMT

10988

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/20/2005 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/20/2005 2:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3330' and dumped 5 sxs cement.
No Stretch. Perforated at 850' and 310'.
Ran tubing to 1700'.
Circulated with 100 sxs 60/40 pozmix - 10% gel cement.
POOH.
Pumped 25 sxs cement down casing - cement circulated up backside.

Perfs:


Top	Bot	Thru	Comments
3379	3381		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 1-19-06

WFL NO 2006060983

RECEIVED

JAN 19 2006

KCC WICHITA

JAN 09 2006

AL TIPTON
BOX 157, HAYS, KS.

#4 MONROE

4-16-13W
900' FSL &
330' FWC, SW

CONTR ALLEN OPLG. CO.

CTY BARTON

GEOL

FIELD TRAPP

K 1929 KB CM 11/21/77 ^{CARD} ISSUED 12/29/77 IP P 28 BOPD + 112 BWPD
ARB 3378-81

+	+	+
+	+	+
+	+	+

API 15-009-21,291

SMP	TOPS	DEPTH	DATUM
ANH	881	+1048	
HEEB	3052	-1123	
TOR	3074	-1145	
DOUG	3089	-1160	
LANS	3134	-1205	
BKC	3329	-1400	
CONG	3355	-1426	
ARB	3378	-1449	
RTD	3381	-1452	

8-5/8" 327, 4 1/2" 3378
DST (1) 3356-81/45-45-45, 310' GMO,
120' GO, SIP 1101-1101#, FP 51-
122#, 143-204#
MICT - CO TD, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

NOV 1977
NOV 1977
NOV 1977