

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ⁰² 15-009-20537-00-00
Spot: E2SWSW Sec/Twnshp/Rge: 4-16S-13W
660 feet from S Section Line, 690 feet from W Section Line
Lease Name: MONROE Well #: 1
County: BARTON Total Vertical Depth: 3388 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------------|
| PROD | 5.5 | 3385 | 0 | w/75 sxs cmt |
| SURF | 8.625 | 347 | 0 | w/200 sxs cmt #110" |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2005 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2005 10:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Sanded to 3350' and dumped 5 sxs cement.
No stretch. Perforated at 1700' - 850' - 320'.
Ran tubing to 1700'.
Circulated with 100 sxs 60/40 pozmix - 10% gel cement.
POOH.
Tied onto casing and pumped 65 sxs cement.
Backside circulated and shut in.
Max. P.S.I. 500#. S.I.P. 250#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Case Morris

(TECHNICIAN)

¹⁰⁹
INVOICED

RECEIVED

DATE 1-19-06

JAN 19 2006

JAN 09 2006

INV. NO. 20060609

KCC WICHITA

JAYHAWK OIL CO. #1 MONROE 4-16-13W
 WICHITA, KANSAS E/2 SW SW
 CONTR H-30, INC. CTY BARTON
 GEOL JIM DEVLIN FIELD TRAPP

E 1929 KB CM 10/8/70 ^{CARD}ISSUED 1/7/71 IP P 28 BOPD + 40 BWPD
 ARB 3385 $\frac{1}{2}$ -3388

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

API 15-009-20,537

| SMP | TOPS | DEPTH | DATUM |
|--------|------|-------|-------|
| ANHY | 883 | +1046 | |
| B ANHY | 914 | +1015 | |
| HEEB | 3053 | -1124 | |
| TOR | 3075 | -1146 | |
| DOUG | 3090 | -1161 | |
| BR LM | 3133 | -1204 | |
| LKC | 3144 | -1215 | |
| BKC | 3340 | -1411 | |
| ARB | 3383 | -1454 | |
| RTD | 3388 | -1459 | |
| | | | |
| | | | |
| | | | |
| | | | |

8 5/8" 347/200sx; 5 $\frac{1}{2}$ " 3385 $\frac{1}{2}$ /75sx
 DST(1) 3366-88/1', 375'MO, BHP 1017-
 1017#/30", FP 20-180#

MICT, CO TD SD/12 FU 1000'WTR + 1200'
 OIL, SWB 7BFP/7HRS 30%OIL

NO LOG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS