

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21087-00-00
Spot: NWNESE Sec/Twnshp/Rge: 16-16S-13W
2310 feet from S Section Line, 990 feet from E Section Line
Lease Name: KRUG Well #: 1
County: BARTON Total Vertical Depth: 3392 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3388	0	125 SX CMT
SURF	8.625	363	0	225 SX CMT

110 24

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2005 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2005 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3340' and dumped 5 sxs cement.
Cut at 1800'.
Pulled to 1700'.
Pumped 100 sxs 60/40 pozmix - 10% gel cement.
Pipe stuck.
Cut at 850' - pumped 40 sxs cement.
Cut at 370' - pumped 30 sxs cement.
Cut at 200' - circulated with 45 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3391	3392		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

110.
INVOICED
DATE 1-19-06
INV. NO 2006060983

RECEIVED
JAN 19 2006
KCC WICHITA

JAN 09 2006

