

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21657-00-00
Spot: N2SWSE Sec/Twnshp/Rge: 16-16S-13W
990 feet from S Section Line, 1980 feet from E Section Line
Lease Name: KRUG A Well #: 1
County: BARTON Total Vertical Depth: 3409 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3408	0	125 SX CMT
SURF	8.625	307	0	200 SX CMT # 110 79

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2005 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-2169

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2005 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3360' and dumped 5 sxs cement.
Cut casing at 1700'.
Pumped 115 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Cut casing at 850'.
Pumped 40 sxs cement with 100# hulls.
Cut casing at 350'.
Pumped 30 sxs cement.
Pulled to 200' and circulated with 50 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3408	3409		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed CASE MORRIS
(TECHNICIAN)

110
INVOICED
DATE 1-19-06
INV. NO 2006060983

RECEIVED
JAN 19 2006
KCC WICHITA

Form CP-2/3

JAN 09 2006

