

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20556-00-00
Spot: NWNE Sec/Twnshp/Rge: 14-18S-32W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: RINEY Well #: 1
County: SCOTT Total Vertical Depth: 4664 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		2350		WITH 325 SX CMT
PROD	4.5	4120	0	WITH 510 SX CMT
SURF	8.625	223		WITH 190 SX CMT

#15158

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2005 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: SHAWN DEVLIN Company: VIKING RESOURCES Phone: (316) 262-2502

Proposed Plugging Method: PUMP 30 SX CMT & 200# HULLS ON BOTTOM. 18 BBL WATER SPACER. 130 SX CMT TO SURFACE. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2005 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 30 SX WITH 100# HULLS AHEAD AND 200# HULLS MIXED IN CMT. PUMP 18 BBL WATER SPACER TO 2300'. PUMP 150 SX CMT. CMT CIRCULATED FROM 2300' TO SURFACE. STAYED FULL. PUMP 10 SX CMT DOWN ANNULUS. PRESSURED TO 500# & HELD.


Perfs:

Top	Bot	Thru	Comments
3940	3945		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
JAN 25 2006
KCC WICHITA

INVOICED

DATE 1-25-06
INV. NO. 2006061011

Form CP-30