

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22951-00-00  
Spot: W2SE Sec/Twnshp/Rge: 6-32S-13W  
1320 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: DUGAN TRUST B Well #: 4  
County: BARBER Total Vertical Depth: 4600 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: 155 N. MARKET - SUITE 800 PO BOX 4  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	272		

\$149<sup>50</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/14/2006 7:00 AM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: JOE Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 630' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE  
Date/Time Plugging Completed: 01/14/2006 10:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:  
1ST PLUG AT 630' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:  
  
**INVOICED**  
DATE 1-25-06  
INV. NO 2006061009

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.  
Plugged through: DP

District: 01  
**RECEIVED**  
JAN 20 2006  
KCC Dodge City

Signed Jerry W. Stapleton (TECHNICIAN) PIET JT  
**RECEIVED**  
JAN 25 2006  
KCC WICHITA