

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-25846-00-00
Spot: NENWNW Sec/Twnshp/Rge: 8-34S-11E
4640 feet from S Section Line, 4580 feet from E Section Line
Lease Name: CASEMENT, BETTY Well #: 7
County: CHAUTAUQUA Total Vertical Depth: 1341 feet

Operator License No.: 7644
Op Name: MILLER, BOBBY ELZO
Address: 2061 INDEPENDENCE RD, UNIT 23
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1341	0	
SURF	7	40	0	

\$ 43⁵⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2005 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO PUMP CEMENT & GEL FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 12/15/2005 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

BULLHEAD PUMPED 10 SACKS CEMENT DOWN 4.5" CASING TO TD FOR BOTTOM PLUG, THEN GEL SPACER & PRESSURED TO 600#. THEN RAN 1" SPOOL HOSE INSIDE 4.5" TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED SPOOL HOSE & TOPPED-OFF WELL. USED TOTAL OF 50 SACKS CEMENT & 2 SACKS GEL.

Perfs:

Top	Bot	Thru	Comments
1268	1300		

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 17 2006
CONSERVATION DIVISION
WICHITA, KS

Remarks: PLUGGED OLD OIL WELL.

Plugged through: CSG

District: 03

Signed



(TECHNICIAN)

INVOICED
DATE 1-19-06
INV. NO 2006060984