

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23129-00-00
Spot: NENESWNW Sec/Twnshp/Rge: 27-10S-25W
1350 feet from N Section Line, 1250 feet from W Section Line
Lease Name: PFEIFER Well #: 1
County: GRAHAM Total Vertical Depth: 4075 feet

Operator License No.: 33306
Op Name: BLAKE EXPLORATION, LLC
Address: 201 S. MAIN, PO BOX 150
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

#13244

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/20/2006 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LARRY PICKNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 01/20/2006 11:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2200' w/25 sxs.
2nd. Plug at 900' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

RECEIVED
JAN 25 2006
KCC WICHITA

District: 04 Signed [Signature] (TECHNICIAN)

INVOICED
DATE 1-25-06
INV. NO 2006061000
JAN 23 2006