

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23122-00-00
Spot: NENWNW Sec/Twnshp/Rge: 5-8S-21W
400 feet from N Section Line, 920 feet from W Section Line
Lease Name: WEIGANG Well #: 1-5
County: GRAHAM Total Vertical Depth: 3735 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	208	0	160 SX CMT

121 39

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/02/2006 8:00 AM
Plug Co. License No.: 5892 Plug Co. Name: BERENTZ DRILLING CO., INC.
Proposal Rcvd. from: LARRY HIDERLITER Company: BERENTZ DRILLING CO., INC. Phone: (620) 275-9231

Proposed Plugging Method: FILL HOLE WITH ROTARY MUD TO 3670' AND SPOT 25 SX CMT. FILL HOLE WITH ROTARY MUD TO 1715' AND SPOT 25 SX CMT. FILL HOLE WITH ROTARY MUD TO 1150' AND SPOT 100 SX CMT. FILL HOLE WITH ROTARY MUD TO 250' AND SPOT 40 SX CMT. FILL HOLE WITH ROTARY MUD TO 40' AND SPOT 10 SX CMT TO SURFACE. PUT 15 SX CMT IN RAT HOLE.

Plugging Proposal Received By: DAVID WANN Witness Type: NONE
Date/Time Plugging Completed: 01/02/2006 5:00 PM KCC Agent: DAVID WANN

Actual Plugging Report:

Hole reported plugged as above.
Order 215 sx 60/40 pozmix w/6% gell and 1/4 lb flowcel per sack.

Perfs:

Remarks: CEMENTED BY ALLIED CEMENTING.

Plugged through:

RECEIVED
JAN 25 2006
KCC WICHITA

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 1-25-06

INV. NO. 2006060998

Form CP-2/3

JAN 23 2006