


15-065-21325-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County. Sec. 20 Twp. 7S Rge. 24 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NE SW
Lease Owner F & M Oil Company
Lease Name HYDE Well No. 1
Office Address 422 Union Center, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 10-26-80
Application for plugging filed 10-26-80
Application for plugging approved 10-26-80
Plugging commenced 10-26-80
Plugging completed 10-26-80
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas available
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
Producing formation Depth to top Bottom Total Depth of Well 3955'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 3955'

Set 1st plug @ 1000' with 70 sx.
2nd plug @ 240' with 20 sx.
3rd plug @ 40' solid bridge with 10 sx.
Rathole with 5 sx., 50/50 posmix, 6% gel.

Plug was down @ 8:30 p.m. 10-26-80.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 5 1980

CONSERVATION DIVISION
Wichita, Kansas

11-5-80

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 1980

Jeanette A. Metheny
Jeanette A. Metheny Notary Public

My commission expires 08-18-84



15-065-21325-00-00

CONTRACTOR'S WELL LOG

OPERATOR: F & M Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HYDE #1
 LOCATION: NW NE SW, Section 20-7S-24W
 Graham County, Kansas
 SPUD DATE: 10-22-80
 COMPLETION DATE: 10-26-80

0	230	Clay, Sand & Shale
230	250	Blue Shale
250	800	Shale
800	2161	Shale & Sand
2161	2195	Anhydrite
2195	2748	Shale
2748	3715	Shale & Lime
3715	3955	Lime
	3955	RTD

Spud hole @ 3:30 p.m. 10-22-80. Drilled 250' of a 12-1/4" hole. Ran 6 joints of 8-5/8" 20# casing (tally 240.97') Set @ 247' RTD. Cement with 190 sx. of common, 3% c.c., 2% gel. Cement did circulate. Plug was down @ 6:30 p.m. 10-22-80.

T.D. 3955'. Set 1st plug @ 1000' with 70 sx., 2nd plug @ 240' with 20 sx., 3rd plug @ 40' solid bridge with 10 sx. Rathole with 5 sx., 50/50 posmix, 6% gel. Plug was down @ 8:30 p.m. 10-26-80.

SAMPLE TOPS:

Anhydrite 2161'
 B/Anhydrite 2195'

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)


NOV - 5 1980
 11-5-80
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the HYDE #1, NW NE SW, Section 20-7S-24W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 4th day of November, 1980.



Jeanette A. Metheny
 Jeanette A. Metheny, Notary Public