

15-065-21188-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 8 Twp. 7S Rge. 24W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SE NW SW

Lease Owner Suburban Propane Gas Corporation  
Lease Name BORN Well No. 1  
Office Address P. O. Box 17689, San Antonio, Texas  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed Feb. 16 19 80  
Application for plugging filed (verbally) Feb. 16 19 80  
Application for plugging approved (verbally) Feb. 16 19 80  
Plugging commenced Feb. 16 19 80  
Plugging completed Feb. 16 19 80  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4320'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

T.D. 4320'  
Set 1st plug at 1200' with 70 sacks  
2nd plug at 240' with 20 sacks  
3rd plug at 40' solid bridge with 10 sacks  
rathole with 5 sacks.  
Cemented with 50/50 posmix, 6% gel.  
Plug was down at 9:20 a.m., 02-16-80.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of February, 1980



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

RECEIVED  
STATE CORPORATION COMMISSION

FEB 22 1980

CONSERVATION DIVISION  
Wichita, Kansas

2-22-80

15-065-21188-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Suburban Propane Gas Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	Born #1
LOCATION:	C SE NW SW, Section 8-7S-24W Graham County, Kansas
SPUD DATE:	February 10, 1980
COMPLETION DATE:	February 16, 1980

0	160	Surface clay and shale
160	240	Sand
240	260	Shale
260	1763	Shale and sand
1763	2250	Shale
2250	2283	Anhydrite
2283	3257	Shale
3257	3445	Shale and lime
3445	3604	Lime
3604	3964	Lime and shale
3964	4180	Lime
4180	4320	Lime and shale
	4320	Rotary Total Depth

Spud hole at 6:45 p.m., February 10, 1980. Drilled 260' of 12 1/4" hole. Ran 6 joints of 8-5/8" - 23# casing. (Talley 250'). Set at 257' with 200 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 12:25 a.m., February 11, 1980.

T.D. 4320'. Set 1st plug at 1200' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 9:20 a.m., February 16, 1980.

SAMPLE TOPS:

Anhydrite 2250'  
B/Anhydrite 2283'


STATE OF KANSAS )  
 ) ss  
COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Born #1, C SE NW SW, Section 8-7S-24W, Graham County Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
Jack L. Partridge  
Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 20th day of February, 1980.



Sherrie L. Brooks RECEIVED  
Sherrie Brooks, Notary Public COMMISSION

My commission expires 08-21-82.

FEB 20 1980

2-22-80  
SHERRIE L. BROOKS  
Notary Public  
Sedgwick County, Kansas