


15-065-00726-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 22 Twp. 7 Rge. 24 (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NE SE
Lease Owner Veeder Supply & Development Co. et al
Lease Name Criswell Well No. 1
Office Address Box 201, Cherryvale, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Sept. 16 19 55
Application for plugging filed Sept. 16 19 55
Application for plugging approved Sept. 16 19 55
Plugging commenced Sept. 16 19 55
Plugging completed Sept. 16 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4302 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	249	cemented w/130 sacks cement

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 240' with 1/2 sack hulls, 15 sacks cement. Filled up to 40' with 1/2 sack hulls and heavy mud. Set plug with 10 sacks of cement. Cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

SEP 23 1955

CONSERVATION DIVISION
Wichita, Kansas

9-23-55

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Veeder Supply & Development Co.
Address P. O. Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
Leo C. Veeder (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo C. Veeder
Cherryvale, Kansas (Address)


SUBSCRIBED AND SWORN TO before me this 22nd day of September, 19 55

My commission expires July 11, 1956 Leo Lawson Notary Public.

PLUGGING
FILE SEC T R
BOOK PAGE --- LINE ---

15-065-00726-00-00

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

North American Car Corporation
Producers Pipe & Supply Co.

Drilled for Veeder Supply & Development Co. Farm Criswell No. 1 Depth 4302'

Contractor Veeder Supply & Development Co. Pipe 249' 8 5/8" csg. cemented w/130 sacks cemen

Location SW/4 NE/4 SE/4 Sec. 22 Twp. 7 Range 24

Commenced 9-3-1955 Completed 9-16-1955 County Graham State Kansas

Cellar	0	9	9	TOPS:	
Soil and clay	9	90	81	Topeka	3528
Sand, shale	90	120	30	Heebner shale	3745
Sand	120	160	40	Toronto Lime	3767
Blue shale	160	245	85	Lansing KC	3780
Shale	245	560	315	Base KC	3991
Sand	560	700	140	Conglomerate	4196
Shale	700	1050	350		
Shale, sand streaks	1050	1550	500		
Shale	1550	1740	190		
Sand	1740	1960	220		
Shale	1960	2005	45		
Red bed, shale	2005	2178	173		
Anhydrite	2178	2215	37		
Shale	2215	2225	10		
Shale and shells	2225	2415	190		
Lime, shale	2415	2545	130		
Lime, shale streaks	2545	2630	85		
Lime, shale	2630	3145	515		
Shale	3145	3200	55		
Lime	3200	3445	245		
Lime and shale	3445	3625	180		
Lime	3625	3970	345		
Lime and shale	3970	4050	80		
Lime	4050	4100	50		
Lime and shale	4100	4170	70		
Lime	4170	4196	26		
Conglomerate	4196	4240	44		
Lime, shale, chert	4240	4250	10		
Chert and shale	4250	4270	20		
Lime, shale cherty	4270	4282	12		
Shale, cong. cherty	4282	4292	10		
Arbuckle	4292	4302	10		
T. D.	4302				

Dry and abandoned

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

Leo C. Veeder, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and on oath hereby states that the above drilling log covering the Criswell #1 well located in Section 22-7-24 Graham County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.
BY Leo C. Veeder
Leo C. Veeder

Subscribed and sworn to before me this 22nd day of September, 1955.

Leo Lawson
Notary Public

PLUGGING
FILE SEC 20-77 240
BOOK 2 LINE 13

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1955
CONSERVATION DIVISION
Topeka, Kansas
923-55