


15-065-00496-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

GRAHAM County. Sec. 17 Twp. 7S Rge. 24 (#) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner PETROLEUM, INC.

Lease Name KOBLER Well No. 1

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JUNE 19 1958

Application for plugging filed JUNE 20 1958

Application for plugging approved JUNE 19 1958

Plugging commenced JUNE 19 1958

Plugging completed JUNE 19 1958

Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well A. D. FABRICIUS, BOX 731, HILL CITY, KANSAS

Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4270 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	261.18'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUD UP WITH HEAVY MUD TO 600' FOLLOWED BY A WOODEN PLUG, PLACED 25 SACKS CEMENT THROUGH DRILL PIPE ON TO PLUG, MUD UP TO 265' FOLLOWED BY A WOODEN PLUG, PLACED 15 SACKS CEMENT THROUGH DRILL PIPE ON TO PLUG, MUD UP TO 40' FOLLOWED BY A WOODEN PLUG, CEMENT TO BASE OF WELL CELLAR WITH 10 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GARVEY DRILLING COMPANY 72-58
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of June, 1958

My commission expires July 11, 1960

Jed A. Brown
Notary Public.

PLUGGING
FILE SEC 17 T 7 R 24W
BOOK PAGE 110 LINE 9

WELL LOG

15-065-00496-00-00

COMPANY PETROLEUM, INCORPORATED

SEC. 17 T. 7S R. 24W

FARM KOBLER NO. 1

LOC. SW, SW, SW


TOTAL DEPTH 4270'

COUNTY GRAHAM CO., KANSAS

COMM. June 11, 1958 COMP. June 19, 1958

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8 5/8" @ 267' W/175 sax.



ELEVATION 2494' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

223	Surface soil & sand
570	Blue shale
600	Shale, sand
1350	White shells, sand & shale
1575	Sand & shale
1635	Blue & green shale
1755	Shale
1860	Red bed & shale
2190	Red bed
2227	Anhydrite
2473	Shale
2785	Shale, shells & lime streaks
2935	Shale w/lime streaks
3120	Shale w/sand streaks
3245	Shale w/sand & lime streaks
3350	Shale & lime streaks
3500	Shale & lime
3600	Lime & shale streaks
3700	Lime & shale
4145	Lime
4227	Lime & shale
4270	Conglomerate
4270	T. D.

State of KANSAS
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 KOBLER well

Subscribed and sworn to before me this 24th day of June 19 58

My Commission Expires: November 12, 1958

STATE COMMISSION

JUL 2 1958

7-2-58

CONSERVATION DIVISION
Wichita, Kan.

PLUGGING
FILE SEC 17 T 7 R 24W
BOOK PAGE 110 LINE 9

Verne A. Morris

[Signature]
NOTARY PUBLIC