

15-065-00074-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Graham County, Sec. 1 Twp. 7 Rge. 24 (E) (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines SE SW SW

Lease Owner Wilcox Oil Company

Lease Name Chase # Well No. 1

Office Address P.O. Box 1440, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9/25 19. 48

Application for plugging filed 9/25 (verbally) 19. 48

Application for plugging approved 9/25 (verbally) 19. 48

Plugging commenced 9/25/48 19.

Plugging completed 9/25/48 19.

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19.

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4320 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	180	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled with Heavy mud to 180 Ft. Wood Plug
and 15 sacks cement, filled with heavy mud to
30 ft. , wood plug and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Wilcox Oil Company
Address P.O. Box 1400, Tulsa, Oklahoma

STATE OF KANSAS COUNTY OF RUSSELL
C. H. ROBERTS (employee of owner) or (owner or operator) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

SUBSCRIBED AND SWORN to before me this 1st day of October 19. 48

[Signature] Notary Public.

My commission expires 6/17/50



10-4-48

15-065-00074-00-00

Chase #1
Wilcox Oil Company

SE SW SW
Sec. 1 Twp. 7 Rge. 24
County: Graham, Kansas

Total Depth: 4320'
Comm: 9/12/48 Comp: 9/26/48

From top of rotary bushing:
Top Lansing K.C. - 3806
Top Conglomerate - 4208
Top Arbuckle - 4290

Casing
8 5/8" Set @ 180'

Cement
140 Sx - Circulated

Formation:	Depth:
Surface Soil & Clay	20'
Shale & Shells	55
Sand	75
Shale & Sand	98
Shale & Shells	180
Sand	230
Shale	438
Shale & Shells	1050
Sand	1080
Shale & Shells	1140
Sand	1205
Shale & Shells	1720
Shale & Iron	1730
sand	1980
Shale & Shells & Red Rock	2000
Sand & Red Rock	2219
Anhydrite	2265
Red Rock, Shale & Shells	2375
Shale & Shells	2900
Shale & Lime	3806
Lime	4182
Lime & Shale	4320

STATE OF KANSAS)
) SS
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Subscribed and sworn to before me this 1st day of October, 1948.

Jane K. ...
Clara ...
Notary Public

My Comm. Expires 6/17/50



10-4-48

PLUGGING
WELL SEC 1 T 7 R 24 W
BOOK PAGE 59 LINE 5