

15-065-00220-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Graham County. Sec. 21 Twp. 7 Rge. 24 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SW NW

Lease Owner Donald D. Dodge & Empire Drilling Company

Lease Name E. P. Goddard Well No. 1

Office Address 1121 Union Nat'l. Bk. Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-9- 19 52

Application for plugging filed 8-9- 19 52

Application for plugging approved 8-9- 19 52

Plugging commenced 8-9- 19 52

Plugging completed 8-9- 19 52

Reason for abandonment of well or producing formation.....

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation..... Depth to top..... Bottom..... Total Depth of Well 4335 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Pipe	0	184	8-5/8	184	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Set plug at 175', 1/2 sack of hulls and 15 sacks of cement. Filled hole to 40', set plug and cemented with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company 8-16-52

Address 1121 Union National Bank Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

I, Dan J. Kornfeld, ~~owner or operator~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld

1121 Union Nat'l. Bk. Bldg., Wichita, Ks.

(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of August, 19 52

My commission expires May 5, 1956

Mary Weimer
Notary Public.

PLUGGING
FILE SEC 21 T 7 R 24
BOOK PAGE 80 LINE 35

23-3390-s 6-51-20M

COMPANY: Donald D. Dodge & Empire Drilling Company
 CONTRACTOR: Empire Drilling Company
 FARM: E. P. Goddard
 LOCATION: NW SW NW, Sec. 21-7-24W, Graham County, Kansas
 COMMENCED: 7-26-52
 COMPLETED: 8-9-52

0	to	30	Surface Clay
30	to	75	Sand
75	to	193	Clay
193	to	2020	Shale and Shells
2020	to	2100	Shells and Shale
2100	to	2140	Anhydrite
2140	to	2180	Shale and Shells
2180	to	2515	Shale and Lime
2515	to	2640	Lime and Shale
2640	to	2800	Shale and Lime
2800	to	2900	Lime and Shale
2900	to	3090	Shale and Lime
3090	to	3170	Lime and Shale
3170	to	3590	Shale and Lime
3590	to	3640	Lime and Shale
3640	to	3710	Shale and Lime
3710	to	3885	Lime
3885	to	4010	Lime and Shale
4010	to	4085	Shale
4085	to	4156	Lime and Shale
4156	to	4300	Shale and Lime
4300	to	4335	Lime (Arbuckle)
4335			R.T.D.

Set at 184' - 8-5/8" Casing - cemented with 135 sacks of cement.

D.S.T. #1 - 3713' - 3739'
 D.S.T. #2 - 3765' - 3775'
 D.S.T. #3 - 3840' - 3856'

Schlumberger Electric Log - 4335'

TOPS: Anhydrite 2100'; Topeka 3498'; Heebner 3653'; Toronto 3678';
 L.S. 3694'; Base of K.C. 3897'; Marmaton 3926'; Cherty
 Conglomerate 4132'; Mississippian 4154'; Kinderhook (?)
 4176'; Simpson 4250'; Arbuckle 4284'.

ELEVATION: 2426 Rotary Bushings
 DRY

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log of the E. P. Goddard #1 in Section 21, Township 7, Range 24 West, Graham County, Kansas as reflected by files of the Empire Drilling Company.

PLUGGING
 FILE SEC 21 T 7 R 24W
 BOOK PAGE 36 LINE 35

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me a Notary Public, within and for Sedgwick County, Kansas, this 15th day of August, 1952.

AUG 16 1952
 CONSERVATION DIVISION
 WICHITA, KANSAS
Mary Heimmer
 NOTARY PUBLIC

My Commission Expires May 5, 1956

81652