

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-22,224-00-00

LEASE NAME Rice Trust

WELL NUMBER 1

SPOT LOCATION 160' W of SW NE SE

SEC. 35 TWP. 7S RGE. 24W (E) or (W)

COUNTY Graham

Date Well Completed 8-25-85

Plugging Commenced 8-25-85

Plugging Completed 8-25-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR D. R. Lauck Oil Company, Inc.

ADDRESS 221 S. Broadway, Suite 400, Wichita, Kansas 67202

PHONE #(316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #6, Hays, KS

Is ACO-1 filed? Yes If not, is well log attached?

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0'	262'	8-5/8"	254.99'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged with 20 sacks cement at 2125'; 100 sacks cement and 1 sack FloSeal at 1260'; 40 sacks cement at 300'; solid bridge plug and 10 sacks cement at 40'; 15 sacks cement in rat hole (60-40 Pozmix Cement, 6% Gel).

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. \_\_\_\_\_  
Address Box 31, Russell, Kansas 67665


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John D. Knightley (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 221 S. Broadway, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 16th day of September, 1985

RECEIVED Stella J. Lipps  
STATE CORPORATION COMMISSION Notary Public



SEP 18 1985  
SEP 18, 1985