

15-065-21248-00-07

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Graham SEC. 36 TWP. 7S RGE. 24W E/W  
Location as in quarters or footage from lines:  
SW SW SE


Lease Owner Abercrombie Drilling, Inc.  
 Lease Name Ray #1 Well No. \_\_\_\_\_  
 Office Address 801 Union Center Wichita, Kansas 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 2-19-82  
 Plugging completed 2-24-82  
 Reason for abandonment of well or producing formation  
XXXXXXXXX Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3850'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	165'	none
				4-1/2"	3849'	1821'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

3550'  
Plugged off bottom with sand to ~~3600'~~ and ran 4 sacks cement. Shot casing @3015', 1935',  
and 1819'. Pulled a total of 62 joints of pipe. Plugged well with 4 sacks hulls, 12 sacks  
gel, 70 sacks 50/50 pos, 4% gel, 3% cc., 1 sack hulls, 7 sacks gel, 70 sacks 50/50 pos,  
4% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the


above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 4 1982  
MAR 4 1982

(Signature) R. Darrell Kelso  
Box 176 Chase, Kansas 67524  
(Address)

CONSERVATION DIVISION  
SUBSCRIBED AND SWORN to before me this 3rd day of March, 19 82

My Commission expires:



Irene Hoover  
Notary Public.

DRILLING LOG

Company: Woodman & Tannitts and Brown Drilling Co.  
 Lease: ~~71 HARRIS~~ - SW 37 1/2 Sec. 34-7-21W  
*Ray# 1* Graham County, Kansas  
 Contractor: Woodman & Tannitts Drilling Company  
 P. O. Box 367, Holisington, Kansas  
 Date Commenced: November 25, 1958  
 Date Completed: December 2, 1958  
 Total Depth: 3850'  
 Casing: 8 5/8" at 165' with 130 sacks cement

Figures indicate the bottom of formation

0 - 35	Sand	3075	Lime & Shale
85	Post Rock	3145	Lime
100	Sand	3295	Shale & Lime
165	Shale	3400	Shale & Lime
1100	Shale & Sand	3480	Lime
1375	Shale & Shells	3585	Lime & Shale
1520	<b>Hard Lime</b>	3650	Lime
1570	Shale & Sand	3837	Lime
1590	Shale & Shells	3850	Shale
2025	Shale & Red Bed		
2070	Anhydrite		
2395	Shale & Shells		

GEOLOGICAL TOPS

Elevation	2358 RB
Anhydrite	2035 /323
Heebner	3586 -1228
Lansing	3620 -1262
Base/Kansas City	3831 -1473
Total Depth	3850 -1492

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops to the best of my knowledge and belief.

WOODMAN & TANNITTS DRILLING CO.

By: K. T. Woodman

K. T. WOODMAN

**PLUGGING**

FILE SEC. 36 T. 7 R. 24W  
 BOOK PAGE 1 LINE 42

Received  
 Mar 4, 1982