

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-065-02960-00-00

Well was completed on:
 API NUMBER 11-5-1958

LEASE NAME Nana NW Unit

WELL NUMBER 101

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 32 TWP. 7S RGE. 24 (W)

COUNTY Graham

Date Well Completed 11-5-1958

Plugging Commenced 7-8-1988

Plugging Completed 7-8-1988

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE# (405) 949-4268 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 26, 1988 (date)

by Mr. Carl Goodrow of District #4 (KCC District Agent's Name).

Is ACO-1 filed? Well was completed on: 11-5-1958 If not, is well log attached? Yes

Producing Formation Lansing-Kansas City Depth to Top 3749' Bottom 3862' T.D. 3920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-Kansas City	Oil	3749	3862	8-5/8"	227'	0
				5-1/2"	3920'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Ran in hole & perforated Anhydrite at 2050' w/4 SPF & Dakota at 1200' w/3 SPF. Pumped down 5-1/2" csg. w/300 sx 65/35 cmt. w/10% gel +2% Econ. +5 sx hulls, filling 5-1/2" csg. to surface. Pumped down annulus w/50 sx cmt., filling to surface. P&A Completed.

State Witness: Mr. Carl Goodrow

Name of Plugging Contractor Halliburton Service Company License No. _____

Address Oberlin, Kansas 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 88

Marsha G. Wilson
 Notary Public

My Commission Expires: 4-1-92

RECEIVED
 AUG 25 1988
 AUG 25 1988
 CONSERVATION DIVISION
 Wichita, Kansas