


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 32 Twp. 7S Rge. 24W (E) (W)
Location as "NE/CNW/SW" or footage from lines C S/2 SE/4
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Clubb Well No. 2
Office Address 780 Fourth National Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 15 19 59
Application for plugging filed March 15 19 59
Application for plugging approved March 15 19 59
Plugging commenced March 15 19 59
Plugging completed March 15 19 59
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3835 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	214'	214'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set No. 1 Plug at 550' with 20 sacks cement; Set No. 2 Plug at 210' with 20 sacks cement; Set No. 3 Plug at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1959
MAR 26 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of owner or power operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: [Signature] V-P
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of March 19 59

My commission expires July 7, 1962
Mona L. Latier Notary Public.

PLUGGING
FILE SEC. 32 T. 7 R. 24w
BOOK PAGE 24 LINE 32

DRILLER'S LOG

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 26 1959
 MAR 26 1959
 CONSERVATION DIVISION
 Wichita, Kansas

Imperial Oil of Kansas, Inc.
 780 Fourth National Bldg.
 Wichita 2, Kansas

Club No. 2
 C S/2 SE/4 Sec. 32-7S-24W
 Graham County, Kansas

Total Depth: 3835'

Commenced: 3-7-59 Completed: 3-15-59

Elevation: 2359' RB
 Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
 Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 214' with 165 sacks cement.

Figures indicate bottom of formations:

Surface Sand, Clay & Shale	214'
Shale & Shells	1610'
Dakota Sand	1800'
Shale & Red Beds	1880'
Shale & Shells	2035'
Anhydrite	2067'
Shale & Shells	2560'
Lime & Shale	3485'
Lime	3835'
Total Depth	3835'

TOPS

Anhydrite	2035'	(/ 324)
Heebner	3597'	(-1238)
Toronto	3620'	(-1261)
Lansing	3632'	(-1273)
Rotary Total Depth	3835'	(-1476)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *W. L. Brown*
 Vice-President

Subscribed and sworn to before me this 24th day of March, 1959.

My Commission Expires:
July 7, 1962

Moral S. Kauter
 Notary Public

PLUGGING
 FILE SEC. 32 T. 7 R. 24W
 BOOK PAGE 24 LINE 32