

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 065-22778 0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR American Energies/American Energies Corp. KCC LICENSE # 5399
(owner/company name) (operator's)

ADDRESS 155 North Market, Suite 710 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 263-5785

LEASE Trexler "A" WELL# 1 SEC. 10 T. 7s R. 23 (~~XXX~~West)

20'E - NE - NW - SE SPOT LOCATION/QQQQ COUNTY Graham

2310 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

1630 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 205.56 CEMENTED WITH 140 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____ 11-19-96

ELEVATION 2340/2348 T.D. 3850 PBD _____ ANHYDRITE DEPTH (2034-2069)
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING (1st Plug @ 2050' w/25sks)(2nd Plug @ 1240' w/100sks)

(3rd Plug @ 255' w/40sks)(4th Plug @ 40' w/10sks)(10sks In Mouse Hole)

(15sks In Rat Hole) 200sks 60/40Poz 6%Gelw/1/4#FS/sk Completed @ 11:00AM 11/5/96

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Thomas Alm PHONE# 913 625-5183

ADDRESS 1922 Whittier City/State Hays, Kansas 67601

PLUGGING CONTRACTOR Dscovery Drilling, Inc. KCC LICENSE # 31548
(company name) (contractor's)

ADDRESS P.O. Box 763 Hays, Kansas 67601 PHONE # (913) 623-2920

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 11/5/96 11:00 AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/18/96 AUTHORIZED OPERATOR/AGENT: Alm De Wood
(signature)