

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 15-065-22,619 ⁰⁰⁻⁰⁰ (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Viking Resources, Inc. OPERATOR'S LICENSE NO. 5011

ADDRESS 105 S. Broadway, Suite 1040, Wichita, KS 67202 PHONE # (316) 262-2502

LEASE (FARM) Seeger WELL NO. 1 WELL LOCATION NE NE NE COUNTY Graham

SEC. 9 TWP. 7S RGE. 23 (E) or (W) TOTAL DEPTH 3800' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 207' CEMENTED WITH 60-40 pozmix SACKS 160

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS _____

PERFORATED AT _____

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 2100' w/25 sx; 2nd plug @ 1300' w/100 sx; 3rd plug @ 250' w/40 sx; 4th plug @ 40' w/10 sx; Rathole 15 sx; 190 sx 60-40 pozmix 6% gel 3% cc, 1 sx Flocel @ 1300'.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No _____
(If not explain.) Sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10:00 a.m. 1-17-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS _____

Harold Maley

PHONE # (313) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: 1-22-91

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1991
1-23-91
CONSERVATION DIVISION
Wichita, Kansas