

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

RECEIVED
STATE CORPORATION COMMISSION

OCT 08 1991

10-8-91
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-065-22,649-00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Griggs Oil, Inc. OPERATOR'S LICENSE NO. 5058

ADDRESS 107 N. Market, #800, Wichita, KS 67202 PHONE # (316) 267-7779

LEASE (FARM) Trexler WELL NO. #1 WELL LOCATION SE SE NE COUNTY Graham

SEC. 4 TWP. 7S RGE. 23 (E) or (W) TOTAL DEPTH 3890' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 212.22' CEMENTED WITH 60-40 posmix-170 sx SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud, set 1st plug @ 2050' w/25 sx; 2nd plug @ 1280' w/100

sx; 3rd plug @ 260' w/40 sx; 4th plug @ 40' w/10 sx w/wiper plug; rathole 15 sx; Total 190 sx 60-40 posmix 6%

gel 2 sx Flocel mixed with cement.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? No

(If not explain.) Sent to Operator to complete.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 2:00 p.m. 9-26-91

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5868

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie RTD, Inc. LICENSE NO. 30684

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: October 7, 1991