

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 COLORADO DERBY BUILDING
200 WEST FIRST STREET
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File one Copy

15-065-02966-00-~~00~~ 00

API Number 15 - (-Completed '55) (of this well)

Lease Owner Cities Service Company

Address 209 E. William, Wichita, Kansas 67202

Lease (Farm Name) Blazier LKC Unit Well No. 302

Well Location 990S - 1650E of N/4 Sec. 28 Twp. 7S Rge. 25 (E) (W) X

County Graham Total Depth 3875' Field Name Blazier

Oil Well X Gas Well Input Well SWD Well Rotary D & A

Well Log attached with this application as required Attached as required

Date and hour plugging is desired to begin April 12, 1982 (Approximate)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Earl Rollings Address Hill City, Kansas

Plugging Contractor Halliburton Services License No.

Address 1100 E. 8th, Hays, Kansas 67601

Invoice covering assessment for plugging this well should be sent to:


Name Cities Service Company

Address 209 E. William, 800 Sutton Place Bldg., Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1982
MAR 24 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: 

~~XXXXXXXXXX~~ Acting Agent

E. W. Peterman

Date: March 22, 1982

55'

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202

March 25, 1982

JOHN CARLIN
C. LOUX
NE T. ROY
WILLIP R. DICK
VROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

THIS PERMIT

JUN 15 1982

EXPIRES

WELL PLUGGING AUTHORITY

Well No.	302
Lease	Blazier LKC (Completed '55)
Description	990'S 1650'E of N/4
Section	28-7-25W
County	Graham
Total Depth	3875'
Plugging Contractor	Halliburton


Cities Service Company
209 E. William
Wichita Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,



DELBERT J. COSTA, Administrator

Mr. Dennis Hamel 806 SW 10th Plainville Ks. 67663 (913)434-7237
is hereby assigned to supervise the plugging of the above named well

NOTE: If you are unable to contact District Plugging Agent at his regular number, call TOLL FREE 1-800-362-1358.

WELL RECORD

Company..... Cities Service Oil Co. et al. Well No. 2 Farm McFadden "B"
 Location..... 990' South and 1650' East of N/4 Cor. Sec. 28 T. 7 R. 25W
 Elevation..... 2538 (2535 Gr.) County Graham State Kansas
 Drlg. Comm. November 29, 1955 Contractor Glenn W. Peel Drilling Company
 Drlg. Comp. December 10, 1955 Acid 1000 gals. 12-17-55
 T. D. 3875' Initial Prod. Physical Potential: 24.5 oil, no water, 24 hrs. (1-4-56)
 P. B. T. D. 3860'

CASING RECORD:

8-5/8" @ 238' cem. 225 sx cement
 5-1/2" @ 3875' cem. 175 sx cement

DV-tool at 2151' with 475 sx cement
 and 225 cu. ft. Stratacrete.

FORMATION RECORD:

shale	0-575
shale & sand	1710
sand	1900
shale	2135
anhydrite	2170
shale	2250
shale & lime	2775
lime & shale	2850
shale & lime	3310
lime	3877

3877 RTD = 3875 SLM

Corr. Topeka	3424'
Corr. Heebner	3621'
Corr. Dodge	3643'
Corr. Lansing	3661'
Corr. Base Kansas City	3862'
Corr. Total Depth	3875'

Drilled cement to 3863 S. L. M.
 Dumped 3 gals. rock on bottom.
 P. B. T. D. 3860 S. L. M.

Perf. 35 shots 3776-86
 60' oil in 1 hr.
 124' oil in 2 hrs.
 215' oil in 3 hrs.
 305' oil in 4 hrs.
 1475' oil in 13 hrs.

ELOPE TESTS (SYFO):	500'	1°
	1000'	1°
	1500'	0°
	2000'	1°
	2500'	1°
	3000'	1°
	3500'	1°

7-7/8" rotary hole.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 24 1982
MAR 24 1982
 CONSERVATION DIVISION
 Wichita Kansas