

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1989
APR 12, 1989
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

Well was completed on
API Number 12-28-55 (of this well). (This must be listed; if no API#
was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000

LEASE/FARM Blazier Unit WELL NO. 303 WELL LOCATION 330' FEL COUNTY Graham

SEC. 28 TWP. 7S RGE. 25 (~~E~~) or (W) Total Depth 3872' PLUG BACK TD 3855'

CHECK ONE:

OIL WELL GAS WELL D & A SWD OR INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 238' CEMENTED WITH 225 SACKS

CASING SIZE 5-1/2" SET AT 3872' CEMENTED WITH 175 SACKS

PERFORATED AT 3724 - 3820' (3 sets)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Procedure is attached for KCC approval.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? NO
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: April 20, 1989

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq
AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Mr. J. D. Hininger PHONE # (913) 674-2182

ADDRESS OXY USA Inc., P. O. Box 38, Hill City, KS 67642

PLUGGING CONTRACTOR Ostrom Well Service Inc. * LICENSE NO. 5680

ADDRESS RR 1 Box 368, Plainville, KS 67663 PHONE # (913) 434-2707

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR
OR AGENT.

SIGNED: Raymond Hill
(Operator or Agent)

DATE: 4-11-1989

*Anticipated Service Co.

(4)

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

THIS NOTICE
JUL 12 1989
EXPIRES

April 12, 1989

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

OXY USA, Inc.
 P. O. Box 26100
 Oklahoma City, OK 73126-0100

Blazier Unit #303
 330' FNL 330' FEL
 Sec. 28-07S-25W
 Graham County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
 Shari Feist Albrecht
 Director

District: #4 2301 E. 13th
 Hays, KS 67601
 (913) 628-1200



MEMORANDUM
OCCIDENTAL OIL AND GAS

Wichita, Kansas
April 4, 1989

TO: Mr. M. D. Harrison
FROM: Mr. P. W. Pringle
SUBJECT: PLUGGING PROCEDURE..... Blazier Unit #303
330' FNL - 330' FEL
Sec. 28-7S-25W
Graham County, Kansas

Well Data:

8-5/8" csg @ 238' w/225 sx
5-1/2" csg @ 3872' w/175 sx
DV Tool @ 2133' w/475 sx (cem circ)
Perforations: 3724-3820' (3 sets)
PBSD 3855'

Shallow Formation Data:

Dakota 1005-1320'
Cheyenne 1340-1640'
Anhydrite 2130-2160'

-
1. Prior to plugging, obtain approval of project from the KCC District Office #4, Hays, KS (913) 628-1200.
 2. Tie onto the 5-1/2" casing, establish rate and fill the long pipe to surface with 65/35 Pozmix w/6% gel + hulls. (approx. 349 sx cement)
 3. Let cement set 48 hrs, check TOC & cap well.

NOTE: Calculations based on 65/35 Pozmix w/6% gel mixed with 100% water/sx cement. Slurry yield 1.97 ft³/sx

PWP/sm

RECEIVED
STATE CORPORATION COMMISSION
APR 10 1989
APR 12 1989
CONSERVATION DIVISION
Wichita, Kansas