

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA, KANSAS 67202

FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1969
CONSERVATION DIVISION
Wichita, Kansas
JAN 24 1969

Lease Owner Chief Drilling Co., Inc. 15-065-20197-0000

Address Box 797 - Great Bend, Kansas 67530

Lease (Farm Name) DAVIS Well No. 1

Well Location S/2 NE SE Sec. 31 Twp. 7S Rge. (E) 25 (W)

County Graham Field Name (If any) _____

Total Depth 3910 Oil Well Gas Well Input Well SWD Well D & A

Was well log filed with application? Yes If not, explain: _____

Date and hour plugging is desired to begin 1/21/69

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of company representative in charge of plugging operations Leo N. Lindenmuth

1200 N. Vine Address Hoisington, Kansas 67544

Plugging Contractor Chief Drilling Co., Inc. License No. _____

Address Box 797 - Great Bend, Kansas 67530

Invoice covering assessment for plugging this well should be sent to Chief Drlg. Co., Inc.

Box 797 Address Great Bend, Kansas 67530

and payment will be guaranteed by applicant.

Signed: Jim Robinson
Applicant or Acting Agent

Date: 1/21/69

15-065-20197-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1969
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

DAVIS #1
S/2 NE SE Sec. 31-7S-25W
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 1-13-69
Completed: 1-21-69

Casing Record: 8 5/8" set @ 208' w/150 sacks Sunset Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface clay & sand	0	43	2439 Gr.
Shale & sand streaks	43	99	2441 D.F.
Shale & sand	99	203	2444 K.B.
Shale	203	210	
Shale-shells	210	1076	
Shale	1076	1700	
Sand	1700	1875	
Red bed-shale & sand streaks	1875	2101	
Anhydrite	2101	2134	
Shale & shells	2134	2180	
Shale	2180	2538	
Shale & lime	2538	2721	
Shale & lime w/sand streaks	2721	2990	
Shale & lime	2990	3758	
Lime	3758	3855	
Lime & shale	3855	3910	
Total Depth	3910		

FORMATION TOPS

	<u>Samples</u>	<u>Log</u>
Anhydrite	2101	2102 + 342
Heebner	3641	3639 -1195
Toronto	3661	3662 -1218
Lansing	3679	3675 -1231
Base KC	3900	3896 -1452
Total Depth	3910	3910 -1466


STATE OF KANSAS, COUNTY OF BARTON: ss

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the S/2 NE SE Sec. 31-7S-25W, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Thomas G. Wesselowski
Thomas G. Wesselowski-Vice President

Subscribed and sworn to before me this 23rd day of January, 1969.



Carmen R. Cook, Notary Public

MY COMMISSION EXPIRES: Dec. 12, 1970