


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-00647-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Graham County. Sec. 7 Twp. 7 Rge. 25 (E) (W) W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE
Lease Owner R. W. Shields & C-G Drilling Co.
Lease Name Best Well No. 1
Office Address 308 Rule Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 27 1960
Application for plugging filed July 27 1960
Application for plugging approved July 27 1960
Plugging commenced July 27 1960
Plugging completed July 27 1960
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	252.63'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 600'. Set plug. Put in 20 sacks cement. Filled to 245'. Set plug. Put in 15 sacks cement. Filled with heavy mud up to 40'. Set Plug. Filled to top with 1/2 sack hulls and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co. 8-1-60
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
G. F. Galloway 107 Rule Building
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 1960

My commission expires May 20, 1963

Vicky Jacobs
Vicky Jacobs Notary Public.



15-065-00647-00-00

W E L L L O G

OPERATOR R. W. Shields & C-G Drilling Co.

SEC. 7-7-25W

WELL NAME Best #1

LOC. NE NE NE

TOTAL DEPTH 3880'

COUNTY Graham

COMM. July 19, 1960

COMP. July 27, 1960

STATE Kansas

RIG NO. 1

ELEVATION 2556' K.B.

CASING: Ran 252.63' (12 jts.) 8-5/8" OD Surface Casing.

PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	435	Shale		
435	1260	Shale-Sand		
1260	1450	Shale		
1450	1510	Sand		
1510	1677	Shale		
1677	1687	Hard Sand		
1687	1930	Sand		
1930	2134	Red Bed		
2134	2174	Anhydrite		
2174	2485	Shell-Shale	0° - 2500	
2485	2635	Shale-Shell	0° - 2750	
2635	3444	Shale-Lime	0° - 3000	
3444	3595	Lime	0° - 3250	
3595	3670	Lime-Shale	0° - 3500	
3670	3727	Lime		DST 3682-3707'
3727	3760	Lime-Shale	0° - 3750	DST 3735-3760'
3760	3834	Lime		
3834	3880	Lime-Shale		

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 1960

CONSERVATION DIVISION
Wichita, Kansas

8-1-60

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

by G. F. Galloway
G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 29th day of July, 1960.

My commission expires:
May 20, 1963

Vicky Jacobs
Vicky Jacobs - Notary public