

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-01311-00-00

API NUMBER _____

LEASE NAME Brandt

WELL NUMBER F 2

SPOT LOCATION C S $\frac{1}{2}$ SW SE

SEC. 7 TWP. 7 RGE. 25 (E) or (W) (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 9-19-88

Plugging Completed 9-19-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3837 $\frac{1}{2}$

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	294			
	Casing	0	3869			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 25 sks. 65/35 posmix, 10% gel, 2% cal, followed by 75 sks. same iwth 400# hulls. Pull 70 jts. tubing. Pump 165 sacks 60/40 posmix, 6% gel with 200# hulls. Circulate to surface. Hook up to 8 5/8 and pump 100 sacks 60/40 pos, 1 sack hulls, 200#. Shut in. Hook to 5 $\frac{1}{2}$ pump 85 sks. 60/40 pos, 6% gel, 1 sk. hulls. Shut in 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364

Address Box 723 Hays, Kansas 67601

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being RECEIVED sworn on oath, says: That I have knowledge of the facts, state STATE CORPORATION COMMISSION herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

ROSEMARY SMITH
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXP. MAY 1, 1991

DEC 5 1988

12-5-88

SUBSCRIBED AND SWORN TO before me this 2 day of December, 1988

Signature) Ted Crawford
(Address) Box 723 Hays, Ks. 67601
Rosemary Smith
Notary Public

My Commission expires: 5/1/1991